F. SUMMARY OF QUALITY IMPACTS

Generally, the water quality at Vernalis has deteriorated since the 1930's. How much degradation has occurred and what have been the principal causes, have been the topics of this chapter. In the analysis of data and interpretation of results, several methods have been employed, sometimes with differing results. The discussion that follows attempts to summarize results and reconcile differences wherever possible. In cases where the methods yield disparate results, ranges are given to include all estimates.

Changes that have occurred in the quality of water at Vernalis between the pre-1944 and post-1952 periods are summarized in tables VI-28 and VI-29. The tables present data derived from the records of mean monthly TDS at Vernalis (mg/L) given in tables VI-13, VI-14, and VI-18. Maximum and mean values are given for three periods--the maximum month, the April-September period and the entire water year--and for each type of year--dry, below normal, above normal and wet.

Data presented in the tables indicate that the TDS at Vernalis has increased in almost all categories listed. The greatest effect is shown in the drier years and the least in the wettest years. Table VI-30 is a composite of tables VI-28 and VI-29, showing the range of estimated impacts at Vernalis. Using the April-September period in a dry year as an example, the mean TDS increased somewhere between 327 and 363 mg/L from pre-1944 to post-1952 years. This increase corresponded to 93 to 116 percent of the pre-1944 period TDS.

As noted in previous discussion, the general deterioration in quality at Vernalis is identified both with reductions in flows along the main stem of the San Joaquin and increases in salt burden transferred to the river. When

Table VI-28. SUMMARY OF IMPACTS ON QUALITY AT VERNALIS
PRE-1944 AND POST-1952

| YEAR TYPE & PERIOD | Total Dissolved Solids, mg/L | | | | Percent Increase | |
| | PRE-1944 | | POST-1952 | | PRE-1944 to POST-1952 | |
	Max	Mean	Max	Mean	Max	Mean
DRY						
Max.month	444	387	951	765	112	98
April-Sept	383	314	830	677	119	116
Full Year	342	288	651	549	99	91
BELOW NORMAL						
Max.month	370	370	729	544	97	47
April-Sept	282	267	683	419	142	46
Full Year	282	261	502	364	78	40
ABOVE NORMAL						
Max.month	517	382	805	641	56	68
April-Sept	244	260	387	325	59	52
Full Year	269	233	489	394	82	69
WET						
Max.month	384	374	462	439	20	17
April-Sept	180	173	226	209	26	21
Full Year	224	197	252	237	13	20
ALL YEARS						
Max.month	517	381	941	584	82	53
April-Sept	383	239	840	433	119	81
Full Year	342	234	651	392	99	65

*BASED ON MOSSDALE DATA

136

TABLE VI-29. SUMMARY OF IMPACTS ON QUALITY AT VERNALIS
PRE-1944 AND POST-1952

| | Total dissolved solids, mg/L | | | | Percent increase | |
| | PRE-1944 | | POST-1952 | | PRE-1944 to POST-1952 | |
Year type and period	Max	Mean	Max	Mean	Max	Mean
DRY						
Max month	616	490	941	765	53	56
Apr-Sept	453	350	840	677	85	93
Full year	374	310	681	549	82	77
BELOW NORMAL						
Max month	407	407	729	544	79	34
Apr-Sept	278	278	683	419	146	51
Full year	262	262	502	364	92	39
ABOVE NORMAL						
Max month	415	398	805	641	94	61
Apr-Sept	236	228	387	325	64	43
Full year	251	229	489	394	95	72
WET						
Max month	366	358	462	439	26	23
Apr-Sept	202	194	226	209	12	8
Full year	207	200	252	237	22	19
ALL YEARS						
Max month	616	424	941	588	53	39
Apr-Sept	453	267	840	434	85	63
Full year	372	254	681	383	82	51

137

TABLE VI-30. RANGE OF ESTIMATED IMPACTS* ON QUALITY AT VERNALIS
(1930-1944) to (1952-1966)

Year type & period	Total dissolved solids, mg/L		Percent increase	
	Max	Mean	Max	Mean
DRY				
Max month	325 – 497	275 – 378	53 – 112	56 – 98
Apr–Sept	387 – 457	327 – 363	85 – 119	93 – 116
Full year	307 – 339	239 – 261	82 – 99	77 – 91
BELOW NORMAL				
Max month	322 – 359	137 – 174	79 – 97	34 – 47
Apr–Sept	401 – 405	132 – 141	142 – 146	46 – 51
Full year	220 – 240	102 – 103	78 – 92	39 – 40
ABOVE NORMAL				
Max month	288 – 390	243 – 259	56 – 94	61 – 68
Apr–Sept	143 – 151	65 – 97	59 – 64	25 – 43
Full year	220 – 238	161 – 165	82 – 95	69 – 72
WET				
Max month	78 – 96	65 – 81	20 – 26	17 – 23
Apr–Sept	24 – 46	15 – 36	12 – 26	8 – 21
Full year	45 – 59	37 – 40	22 – 31	19 – 20
ALL YEARS				
Max month	325 – 497	164 – 203	53 – 112	39 – 53
Apr–Sept	387 – 457	167 – 194	85 – 119	63 – 81
Full year	307 – 339	129 – 158	82 – 99	51 – 68

* Based on results from Mossdale data and load-flow regression data. See
  tables VI-28, VI-29.

the total change in quality at Vernalis that has occurred between the two periods is distributed between reduced flow and increased salt load, it is noted that the effect of increased salt load is becoming relatively more important in recent years. Tables VI-31 and VI-32 summarize the changes in total salt load that have occurred in the two decades 1950-59 and 1960-69 in relation to the period of 1930-49.

In the 1950's, the estimated increased in annual TDS load at Vernalis. In the 1960's the load increased 530 to 569 kilotons TDS per year. This increase between the 1950's and 1960's, a 50-56 percent jump, indicates the more recent impact on water quality at Vernalis. During the 1960's the average annual runoff at Vernalis was about 710,000 acre-feet lower than for the 1930-1949 period while the total TDS load actually increased.

In the 1950's the estimated increase in the April-September TDS load at Vernalis ranged from -18 to +21 kilotons TDS. In the 1960's the load increased +251 to 290 kilotons TDS per year. This increase, 44 to 54 percent of 1930-1949 is indicative also of more recent impacts on Vernalis water quality. During the 1960's the average April-September runoff at Vernalis was about 610 thousand acre-feet lower than in the 1930-1949 period.

A similar analysis based on chloride data summarized in table VI-10, indicates an overall increase in salt load (as chlorides) of about 0-35 percent in the post-1949 years depending on year classification, the dry and below normal years showing the greatest change.

Analysis of the sources of salt load contributing to the San Joaquin River, and which account for, in part, the increases noted at Vernalis, indicates that about 45 to 85 percent of the total load, depending somewhat on the

139

Table VI-31. SUMMARY OF CHANGES IN TDS LOAD AT VERNALIS,
1930-1969

Month of Year	TDS Load, Tons x 10^3		
	1930-49 *	1950-59	1960-69
Oct	41	49	61
Nov	42	66	63
Dec	57	81	90
Jan	71	97	152
Feb	122	98	186
Mar	148	131	208
Apr	140	168	199
May	136	137	207
Jun	155	119	215
Jul	75	58	104
Aug	35	35	47
Sep	35	41	55
Apr-Sep	576	558	827
Percent change from 1930-49	0	-3	44
Year	1057	1080	1587
Percent Change from 1930-49	0	2	50

* Based on Mossdale chloride data

TABLE VI-32.   SUMMARY OF CHANGES IN TDS LOAD AT VERNALIS,
1930-1969

Month of year	TDS load, tons x 10^3		
	1930-49*	1950-59	1960-69
Oct	48	49	61
Nov	44	66	63
Dec	62	81	90
Jan	66	97	152
Feb	108	98	186
Mar	153	131	208
Apr	102	168	199
May	111	137	207
Jun	149	119	215
Jul	94	58	104
Aug	40	35	47
Sept	41	41	55
Apr-Sept	537	558	827
% Change from 1930-49	0	4	54
Year	1018	1080	1587
% Change from 1930-49	0	6	56

* Based on load-flow regression data.

quality constituent considered and the year type, enters within upper San Joaquin River basin. The remaining fraction includes the contributions of the Tuolumne gas wells that have been the subject of efforts by the State of California to reduce point source salt accretions to the river, local drainage returns between Newman and Vernalis and runoff from the east side streams.

Table VI-33 is a summary of the results obtained from salt balances using chloride data for the four representative months of October, January, April, and July. The tabulated results show that virtually no change has occurred in the proportion of salt load contributed by the upper San Joaquin River basin. The table shows that the most apparent changes have taken place on the Tuolumne River and in "other" flows, the unidentified sources and sinks of salt load within the San Joaquin River basin.

Table VI-33 summarizes estimated impacts on the water quality of the San Joaquin River at Vernalis as determined by the two methods, one utilizing the Mossdale chloride data and the second based on chloride load-flow regressions. Data presented in the summary table were derived from various tables presented earlier in this chapter; specifically tables VI-9, 30, 31, 32, and 33 were utilized. Footnotes on table VI-34 describe the procedures used in calculation of the values given.

The effects of upstream development, both in the entire San Joaquin River basin and in the upper San Joaquin River basin as given in table VI-34, are outlined briefly for each year classification as follows:

Dry Years

In dry years the average TDS increase at Vernalis, resulting from development upstream after 1947, was estimated at about 350 mg/L for the April-September

Table VI-33   PERCENT OF VERNALIS CHLORIDE LOAD
AND THEIR ORIGINS*

	Upper San Joaquin River Basin %		"Others" %		Stanislaus River %		Tuolumne River %		Upper San Joaquin plus "others" %	
	Pre	Post	Pre	Post	Pre	Post	Pre	Post	Pre	Post
DRY										
Apr-Sep	107	86	-67	-55	4	2	57	69	40	30
Full Year	72	71	-22	-28	3	2	47	56	50	43
BELOW NORMAL										
Apr-Sep	83	81	-28	-49	3	2	43	66	55	32
Full Year	61	67	-1	-21	3	2	38	52	59	46
ABOVE NORMAL										
Apr-Sep	59	63	17	1	2	3	23	35	75	63
Full Year	51	55	22	9	2	2	26	34	72	64
WET										
Apr-Sep	68	56	37	25	2	3	16	21	82	77
Full Year	47	49	31	25	2	2	21	26	78	73
ALL YEARS										
Apr-Sep	78	73	-11	-24	3	2	35	51	63	48
Full Year	58	62	7	-7	2	2	33	44	65	55

*Based on load-flow regression salt balances.
 Pre refers to 1930-1944 period with 5-Dry, 1-B.Norm., 7-A.Norm., 2-Wet
 Post refers to 1952-1966 period with 4-Dry, 5-B.Norm., 2-A.Norm., 4-Wet

143

TABLE VI-34. SUMMARY OF ESTIMATED IMPACTS ON THE QUALITY OF
THE SAN JOAQUIN RIVER AT VERNALIS

1	2	3	4	5	6	7	8
	Total increase in TDS mg/L at Vernalis	Increase in TDS mg/L due to decreased flow		Increase in total salt load			
				Vernalis total		Increased caused by CVP	
		Percent of Pre-CVP	Percent due to CVP	Increase Tons x 10^3	% of Pre-CVP	Increase Tons x 10^3	% of Pre-CVP
Year Type & Period							
DRY							
Apr–Sep	327 – 363	84 – 100	1.8 – 2.1	68	49	58	42
Full Year	239 – 261	22 – 26	6.3 – 7.4	143	55	102	39
BELOW NORMAL							
Apr–Sep	132 – 141	100	36	95	57	77	46
Full year	102 – 103	100	45	193	62	129	41
ABOVE NORMAL							
Apr–Sep	65 – 97	100	37	33	39	21	25
Full year	161 – 165	100	59	72	46	40	26
WET							
Apr–Sep	15 – 36	81 – 100	45 – 55	76	46	43	26
Full year	37 – 40	65 – 73	44 – 50	143	46	70	23
ALL YEARS							
Apr–Sep	167 – 194	90 – 100	30 – 33	73	49	54	36
Full year	129 – 158	70 – 73	37 – 39	147	53	91	33

Col. 2 – See Table VI-30.
   3 – Obtained by assuming no change in salt load and flow reduction TDS=50 mg/L.
   4 – Col 3 x ratio of upper San Joaquin flow reductions to total San Joaquin flow reduction.
   5 – Obtained by pro-rating average TDS load increase between 1960's and 1930-49 period (Tables VI-31 and 32) in proportion to salt load increase in each year type (Table VI-9) and number of years of each year type in 1950-69 period.
   6 – Col 5 salt load for 1930-49 period x proportion of years in each class.
   7 – Col 5 x proportion of total chloride load contributed by upper San Joaquin basin (Table VI-33)
   8 – Col 7 x proportion of years in each year class.

Table VI-33   PERCENT OF VERNALIS CHLORIDE LOAD
AND THEIR ORIGINS*

	Upper San Joaquin River Basin %		"Others" %		Stanislaus River %		Tuolumne River %		Upper San Joaquin plus "others" %	
	Pre	Post	Pre	Post	Pre	Post	Pre	Post	Pre	Post
DRY										
Apr-Sep	107	86	-67	-55	4	2	57	69	40	30
Full Year	72	71	-22	-28	3	2	47	56	50	43
BELOW NORMAL										
Apr-Sep	83	81	-28	-49	3	2	43	66	55	32
Full Year	61	67	-1	-21	3	2	38	52	59	46
ABOVE NORMAL										
Apr-Sep	59	63	17	1	2	3	23	35	75	63
Full Year	51	55	22	9	2	2	26	34	72	64
WET										
Apr-Sep	68	56	37	25	2	3	16	21	82	77
Full Year	47	49	31	25	2	2	21	26	78	73
ALL YEARS										
Apr-Sep	78	73	-11	-24	3	2	35	51	63	48
Full Year	58	62	7	-7	2	2	33	44	65	55

*Based on load-flow regression salt balances.
Pre refers to 1930-1944 period with 5-Dry, 1-B.Norm., 7-A.Norm., 2-Wet
Post refers to 1952-1966 period with 4-Dry, 5-B.Norm., 2-A.Norm., 4-Wet

143

TABLE VI-34. SUMMARY OF ESTIMATED IMPACTS ON THE QUALITY OF
THE SAN JOAQUIN RIVER AT VERNALIS

1	2	3	4	5	6	7	8
	Total increase in TDS mg/L at Vernalis	Increase in TDS mg/L due to decreased flow		Increase in total salt load			
				Vernalis total		Increased caused by CVP	
		Percent of Pre-CVP	Percent due to CVP	Increase Tons x 10^3	% of Pre-CVP	Increase Tons x 10^3	% of Pre-CVP
Year Type & Period							
DRY							
Apr-Sep	327 - 363	84 - 100	1.8 - 2.1	68	49	58	42
Full Year	239 - 261	22 - 26	6.3 - 7.4	143	55	102	39
BELOW NORMAL							
Apr-Sep	132 - 141	100	36	95	57	77	46
Full year	102 - 103	100	45	193	62	129	41
ABOVE NORMAL							
Apr-Sep	65 - 97	100	37	33	39	21	25
Full year	161 - 165	100	59	72	46	40	26
WET							
Apr-Sep	15 - 36	81 - 100	45 - 55	76	46	43	26
Full year	37 - 40	65 - 73	44 - 50	143	46	70	23
ALL YEARS							
Apr-Sep	167 - 194	90 - 100	30 - 33	73	49	54	36
Full year	129 - 158	70 - 73	37 - 39	147	53	91	33

Col. 2 - See Table VI-30.
   3 - Obtained by assuming no change in salt load and flow reduction TDS=50 mg/L.
   4 - Col 3 x ratio of upper San Joaquin flow reductions to total San Joaquin flow reduction.
   5 - Obtained by pro-rating average TDS load increase between 1960's and 1930-49 period (Tables VI-31 and 32) in proportion to salt load increase in each year type (Table VI-9) and number of years of each year type in 1950-69 period.
   6 - Col 5 salt load for 1930-49 period x proportion of years in each class.
   7 - Col 5 x proportion of total chloride load contributed by upper San Joaquin basin (Table VI-33)
   8 - Col 7 x proportion of years in each year class.

period and 250 mg/L for the full year. Of this increase the proportion due to reduced flow from all sources was 90 percent in the April-September period, but only 25 percent for the entire year. The impact of the CVP on water quality (as expressed by changes in TDS) in dry years, caused by flow reductions in the upper San Joaquin basin, was relatively small, only 2 percent in the April-September period and 7 percent for the entire year.

Salt loads at Vernalis in dry years were estimated to have increased in the period subsequent to 1947, by 68,000 tons in the April-September period and by 143,000 tons for the whole year. These increases corresponded to roughly 49 percent and 55 percent, respectively, of the pre-1944 TDS loads at Vernalis. The CVP salt load impact in dry years was estimated at 58,000 tons in the April-September period and 102,000 tons for the full year, corresponding to 42 percent and 39 percent increases, respectively, of pre-1944 salt loads at Vernalis.

Below Normal Years

In below normal years, the increase in average TDS concentration at Vernalis between the pre- and post-CVP periods was estimated at about 135 mg/L for the April-September period and slightly more than 100 mg/L for the full year. Virtually all of this increase is attributed to reductions in flow from all sources. The impact due to reduced flow attributed to the CVP was about 36 percent in the April-September period and 45 percent for the full year.

TDS load increases in below normal years subsequent to 1947 are estimated at 95,000 tons for the April-September period and 193,000 tons for the year. Of this increase, 77,000 tons and 129,000 tons, respectively, were estimated to have been derived from the upper San Joaquin basin. The proportionate impact

of the CVP on salt loads at Vernalis was largest for below normal years, 46
percent of the total increase at Vernalis in the April-September period and 41
percent for the whole year.

Above Normal Years

In above normal years the average TDS increase at Vernalis, resulting from
development upstream after 1947, was estimated at about 80 mg/L for the April-
September period and 165 mg/L for the full year. Of this increase, the propor-
tion due to reduced flow from all sources was 100 percent in both the April-
September and full year periods. The impact of the CVP on water quality (as
expressed by changes in TDS) in above normal years, caused by flow reductions
in the upper San Joaqin basin, was 37 percent in the April-September period and
59 percent for the entire year.

Salt loads at Vernalis in above normal years were estimated to have increased
in the period subsequent to 1947 by 33,000 tons in the April-September period
and by 72,000 tons for the entire year. These increases correspond to roughly
39 percent and 46 percent, respectively, of pre-1944 TDS loads at Vernalis.
The CVP salt load impact in above normal years was estimated at 21,000 tons in
the April-September period and 40,000 tons for the full year, corresponding to
25 and 26 percent increases respectively, in pre-1944 salt loads at Vernalis.

Wet Years

In wet years, the increase in average TDS concentration at Vernalis between
the pre- and post-CVP periods was estimated at about 25 mg/L for the April-
September period and about 40 mg/L for the full year. Of this increase the
proportion due to reduced flow from all sources was 90 percent in the April-
September period, and 70 percent for the entire year. The impact due to

reduced flow attributed to the CVP was about 50 percent for both the April-September and full year periods.

TDS load increases in wet years subsequent to 1947 are estimated at 76,000 tons for the April-September period and 143,000 tons for the year. Of this increase, 43,000 tons and 70,000 tons, respectively, were estimated to have been derived from the Upper San Joaquin Basin. The proportionate impact of the CVP on salt loads at Vernalis was 26 percent of the total increase at Vernalis in the April-September period and 23 percent for the full year.

CHAPTER VII

EFFECTS OF OPERATION OF CVP AND SWP EXPORTS PUMPS NEAR TRACY

CHANNEL DEPTHS AND CROSS SECTIONS

The geometry of the channels within the southern Delta was studied to determine whether the channel cross sections and bottom elevations have changed since the 1930's in such a way as to alter water circulation patterns and water depths to a degree that modifies the southern Delta water supply.

Channel Surveys

Prior to 1913, most existing channels within the South Delta Water Agency were well defined, due in part to the sidedraft clamshell dredge which was used over many years to construct the levee system within the South Delta and to keep channels clean of sediment. Since 1913 most of the channels in the South Delta have been surveyed several times. The results of surveys are summarized if figure VII-1.

Available survey data include:

Date of survey	Channels surveyed	Source of data
1913	Old River - Middle River to Victoria Canal Middle River - Old River to Victoria Canal Grant Line and Fabian Canals	USCE
1933-34	All SDWA channels	USC&GS
1957	Grant Line and Fabian Canals, plus Salmon Slough and Paradise Cut	DWR
1965	Grant Line and Fabian Canals	USCE
1973	Old River-San Joaquin River to Victoria Canal Middle River-Old River to Victoria Canal Grant Line and Fabian Canals	DWR
1976	San Joaquin River-Vernalis to Mossdale	DWR

149

040725

SALMON SLOUGH & OLD RIVER - SALMON SLOUGH TO SAN JOAQUIN RIVER

OLD RIVER - DMC INTAKE TO SALMON SLOUGH

GRANT LINE & FABIAN BELL CANALS

DISTANCE IN MILES

MAXIMUM DEPTH BELOW LOW WATER SURFACE DATUM IN FEET

S.J. RIVER   MIDDLE R.   SALMON SL.   GRANT LINE CANAL

SALMON SL.   TOM PAINE SL.   TRACY RD.   WESTSIDE L.D.   OLD RIVER

SALMON SL.   TRACY RD.

San Joaquin River – Mossdale to Vernalis

Middle River – Victoria Canal to Old River

Distance in Miles

Maximum Depth Below Low Water Surface Datum in Feet

SOUTH DELTA CHANNEL
DEPTH SURVEYS

Water and Power Resources Ser
Dated April 1980   Figure
(Cont

In describing the geometry of the channels, especially the depth, it
is appropriate to use a fixed reference plane. For example, navigation charges
which need to be site specific use local MLLW. However, this locally oriented
datum varies from -0.2 ft MSL to +0.5 ft MSL within the SDWA and is dependent
upon the condition of San Joaquin River inflow.

Much of the hydrographic data used in this study was taken from charts
used by the Corps of Engineers to build the Sausalito model of the Bay-Delta,
the low water datum, (LWD) of 1.0 foot below mean sea level as shown in the
etch below, which was used by the Corps to integrate data from diverse
...ces, was also adopted for the present study. It is a conservative datum in
that it is lower than the local MLLW levels throughout the SDWA by a foot or
more.

Most of the channels, dredged prior to 1913, were 10 to 20 feet below the
LWD. By 1933-34, however, most channels surveyed had aggraded significantly.
Existing survey data indicate that in some channels, such as the southern
reaches of Middle River, little dredging has been done. Data on dredging to
maintain the levees and to provide fill for road construction were not available.

In the 1973 and 1976 surveys channel geometry was determined for reaches
from Vernalis on the San Joaquin River to the State and Federal pumping plants
near Clifton Court Forebay, including Old River and the Grant Line and Fabian-
Bell Canals, and for the Middle River between Old River and Victoria Canal. To
determine channel bottom profiles, bottom elevations taken at 1/2 to 1-1/2-mile
intervals were averaged. The shapes of the channels studied were such that the
average water depths approximated the hydraulic radius. An example of the
channel mean depths and cross sections observed in the 1973 survey for the

reach of Old River between Clifton Court and the San Joaquin River is presented in figure VII-2.

The diagram below illustrates the differences between average and maximum depths and between LWD and MSL.

Bottom elevations of the major channels were further analyzed in relationship to the survey dates and the initial operations of the Federal and State pumping plants.

San Joaquin River--Vernalis to Mossdale Bridge. Most of this reach has aggraded since the 1933-34 surveys. By 1976 the elevation of the stream bottom had risen 0.5 to 9.5 feet above the 1933-34 levels, with an average increase of about 4.0 feet. The bottom elevation of the reach from Vernalis to a point approximately 4.8 miles north of the San Joaquin River club varied from 2 to 7 feet below the LWD in 1933 and varied from 1.5 to 3.5 feet above LWD in 1976. This aggradation generally causes a corresponding reduction in water depth.

Old River, San Joaquin River to and including Salmon Slough. In 1973, streambed elevations of this 7.5-mile reach were equal to or below that measured in the 1933-34 survey. The 1973 elevations ranged from 8 to 24 feet below LWD with an average of about 14 feet; the 1933-34 elevations varied from 8 to 17 feet with an average of about 10 feet. Therefore, during the intervening

Figure VII-2   CHANNEL PROPERTIES, OLD RIVER, CLIFTON COURT TO SAN JOAQUIN RIVER
(Data from 1973 DWR Survey, Datum is Mean Sea Level)

40 years, the channel had degraded an average of 4 feet, but with very little change in the upstream 1/3 of the reach.

Old River, to Salmon Slough to Delta-Mendota Canal Intake Channel. Bottom elevations of this 11-mile channel averaged 12 feet in 1913, with a range of 9 to 22 feet below LWD. The channel had displayed a 3.5-foot aggradation by the 1933-34 survey. However, the channel had not had any further significant change by the 1973 survey. The 1933-34 and the 1973 surveys each indicated a similar channel restriction near the bifurcation of Old River and Tom Paine Slough. Maximum cross sectional depths measured in 1973 through the 4-mile restricted section averaged about 6 feet with a minimum of 4 feet with reference to LWD elevation. The mean elevation of the bottom of the most restricted area is about 2 feet below mean sea level as shown in figure VII-2. Where as the maximum depth below LWD was about 3.7 feet.

Grant Line and Fabian Canals—In 1913 the elevation of these paralleling 7-mile channels averaged more than 20 feet below LWD. By 1957 they had aggraded about 8 feet with an average depth of 12 feet below LWD, remaining at that depth until after the 1965 survey. By the 1973 survey, however, the channels had degraded to an average of about 16 feet below LWD. The channel depths could have been influenced by maintenance dredging and/or increases in channel velocities due to operation of Clifton Court Forebay. Flow restrictions have not been apparent in these channels.

Middle River—Old River to Victoria Canal—In 1913, the channel elevation of this 11.5-mile reach of Middle River varied between 7 and 18 feet below LWD with an average of about 12 feet below LWD. By the 1933-34 survey, channel bed had aggraded to an average of about 6 feet below LWD elevation. Further

aggradation was shown by the 1973 survey to an average depth of 4 feet below

LWD elevation. However, the 6-mile reach directly north of Old River has only

aggraded about 0.5 feet since the 1933-34 survey. Both the 1933-34 and 1973

surveys recorded a restriction 0.4 of a mile north of the head of Middle River

with maximum depths of 1.0 in 1933-34 and 0.5 feet in 1973, below LWD elevation.

Calculated Hydraulic Resistance in Old River

The resistance to flow, assuming present channel geometry in Old River,

was studied as a basis for examination of the effect of reduced water levels on

water circulation through this channel.

Using channel cross section data obtained by the DWR in 1973, the

hydraulic resistance characteristics were estimated for some 22 channel segments

of Old River between Clifton Court and the main stem of the San Joaquin River.

It can be shown by open channel flow hydraulics that resistance, the relation-

ship between head loss and channel discharge, is proportional to the square of

channel width and the 10/3 power of the mean depth. In essence, this means

that a narrow, shallow channel greatly restricts flow--much more dramatically

than might at first appear to be the case by inspection in the field. For

example, simply reducing channel width and depth by one-half each, thereby

reducing the effective area to one-quarter, increases hydraulic resistance for

the same length and roughness more than 40 times. These effects are

especially evident in the central section of Old River in the vicinity of Tom

Paine Slough where mean channel depths below mean sea level average less than

3 feet and widths are less than 100 feet.

The channel cross sections and depths along Old River are illustrated

graphically in figure VII-2. In figure VII-3 the cumulative hydraulic resistance

Figure VII-3   CUMULATIVE HYDRAULIC RESISTANCE IN OLD RIVER, CLIFTON COURT TO SAN JOAQUIN RIVER

to flow is plotted for the entire channel from Clifton Court to the San Joaquin
River. The same data are visually keyed to a partial map of Old River in
figure VII-4. It is noted that most of the effect, about 90 percent of the
total, is concentrated in a short section about 2 miles long in the vicinity of
Tom Paine Slough. This restriction was evident during the 1933-34 channel
survey. Obviously, this area controls the rate of flow in an east-west direc-
tion through Old River. Actually, it forces the largest proportion of the east
to west flow through Grant Line and Fabian-Bell Canals rather than through the
westerly section of Old River.

Sediment Movement

In 1950, the USBR improved the operation of the Delta-Mendota Canal
intake channel by dredging the Old River Channel to a minus 17-foot elevation
from the Delta-Mendota Canal headworks downstream to approximately Grant Line
Canal. By 1969 the dredged channel was nearly obliterated by sediment which
continued to move into the Delta-Mendota Canal Intake Channel. The Old River
Channel was dredged again in 1969 and in 1974. Another example of sediment
movement is the accumulation of 60,000 cubic yards of sediment in Clifton Court
Forebay during the first 4 years of its operation.

During the same period a large but unestimated amount of sediment was
pumped into the Delta-Mendota Canal as suspended load and deposited within
the canal, O'Neill Forebay and Mendota Pool. The available suspended solids
data for both the DMC and State Aqueduct and vicinity are located in STORET, a
Federal data storage system, and summarized below for the period of record:

Figure VII-4   WATER LEVELS AND CHANNEL CHARACTERISTICS
OLD RIVER--SOUTH DELTA

| Stations | Period of record | Average total suspended solids | |
		mg/L	pounds/acre-foot
DMC near Head	1973 - 1974	42.0	115
Delta Pumping Plant Headworks	1973 - 1979	21.3	58
Clifton Court	1973 - 1979	41.6	114
Old River at Mouth of Clifton Court Intake	1973 - 1974	44.1	120
Old River at Mossdale Bridge	1973 - 1978	48.0	123
Old River opposite Rancho Del Rio (near Rock Slough)	1973 - 1979	23.0	63

The Service and the Department of Water Resources established a Scour Monitoring Program primarily in Old and Middle Rivers north of the pumps to identify any channel scouring. The Department makes soundings repetitively at selected cross sections and the Service makes an annual aerophotographic survey of channels contiguous to the export pumps. Results indicate some degradation and aggradation at the selected cross sections north of the pumping plants, but no overall erosion or scour patterns. There are no stations east of Tracy Road in the South Delta Water Agency in the program.

IMPACT OF EXPORT PUMPS ON SOUTHERN DELTA WATER LEVELS, WATER DEPTHS, AND WATER QUALITY

Impact of Export Pumping on Water Levels and Water Depths

Any diversion from the Delta, including export pumping, lowers the water levels to some distance from the point of diversion, and the lowering of level is superimposed on whatever level would otherwise result from the combination of tides and net advective or downstream flows. The effect of large

diversions from Delta channels is a depression in channel water surface which provides the gradient for the movement of water in all connecting channels toward the pumps. The distribution of flow and the water level drawdown among connecting channels is a function of channel geometry, roughness, pumping rate and in the instance of the SDWA channels, the flows in the San Joaquin River. A generalized impact of operating the CVP and SWP export pumps is a reduction of water levels and a modification of channel flows in the southern Delta.

The Clifton Court Forebay was incorporated into the SWP primarily to allow the use of offpeak power to pump water into the State Aqueduct and to prevent channel scouring prior to the creation of a Delta transfer facility.

Water level data are available in considerable detail at a number of stations throughout the Delta, including nine stations within the southern Delta. Since the drawdown of water level by the export pumps is superimposed on the water level fluctuations that would otherwise occur, two approaches have been used to determine the degree and spatial extent of the drawdown caused by the export pumps. These methods of determination include field tests and mathematical modeling.

Field tests--Steady export pumping field tests were made in May and August of 1968 wherein levels were measured at high and low export pumping rates with other conditions substantially the same. These tests were precipi-tated by concerns that export pumping was a contributing cause of reductions in water level such that the operation of agricultural pumps in Tom Paine Slough and in the southern portion of Middle River was restricted during low tide, and siphons around Victoria Island were losing prime. Reductions in pump capacity due to low water levels were also reported at the Westside Irrigation

District intake on Old River south of Fabian Tract. The test evaluations were limited to low tide levels which were considered by the project operators to represent the periods when steady export pumping has the maximum effect on southern Delta water supply. However, the reduction in channel water supply is also influenced by the reduction in tidal prism upstream from the export pumps and this is related to water level reductions at all levels of tide.

The flows in the San Joaquin River near Vernalis were about 700 and 900 ft^3/s for the May and August testing period, respectively.

These 1968 tests are described and the results summarized in two cooperative reports by DWR and the USBR, both titled "Summary of Effect of Export Pumping on Water Levels in the Southern Delta." One report describes the May 25-30, 1968 tests and was issued in July 1968. The other report describes the August 29 to September 9, 1968 tests and was issued in December 1968. Results of these tests indicated that steady export pumping at the rates observed in the tests lowered the lower low tide level at Clifton Court by 0.07 to 0.08 foot for each 1,000 ft^3/s of export pumping.

The effects of water level depression due to State and Federal export pumping extends northward and eastward from the points of diversion. The 1968 test results in vicinity of Clifton Court, after correction by a constant amount for the normal tidal fluctuation at Antioch (assumed to be outside of the influence of the pumps), are presented in table VII-1.

The general effect of export pumping is to reduce local water levels, creating a gradient toward the point of diversion and redistributing flows in the principal channels of the southern Delta. Depending on the level of export and rate of inflow to the Delta near Vernalis, the effect is sometimes to

TABLE VII-1

1968 PUMP TESTS RESULTS

	1		2		3
	May Test 6725 to 1950 ft³/s Differential (4775 ft³/s)		Aug/Sep Test 6934 to 800 ft³/s Differential (6134 ft³/s)		Difference in water level depression be-tween pump tests [1] Col.1 Col. 2
	Water Level Depression		Water Level Depression		
Stations	Feet	Ft/1000 ft³/s	Feet	Ft/1000 ft³/s	Feet
Old River at Clifton Court	0.33	0.07	0.47	0.08	0.13
Old River at Tracy Road	0.30	0.063	0.40	0.065	0.10
Tom Paine Slough above Mouth	0.29	0.06	0.35	0.06	0.06
Grant Line at Tracy Road	0.30	0.06	0.38	0.06	0.08
Middle River at Bacon Island	0.12	0.03	0.10	0.02	-0.02
San Joaquin River at Mossdale	0.14	0.03	--	--	--
San Joaquin River at Brant Bridge	0.16	0.03	0.12	0.02	-0.04
Old River near Byron	0.29	0.06	0.32	0.05	0.03
Old River near Rock Slough	0.08	0.02	0.12	0.02	0.04
Middle River at Borden Hwy.	0.29	0.06	0.30	0.05	0.01
Rock Slough at CCC Intake	0.15	0.03	0.14	0.02	-0.01

[1] This column illustrates that with an increase in diversion rate of about 1,400 ft³/s the water level depression either decreased or increased only slightly at stations beyond Tom Paine Slough. This is indicative of the significance of pumping impact during the tests at these outlying stations.

reverse the net flow downstream of the bifurcation of the San Joaquin and Old Rivers.

Another examination of recorded water levels was made for the June 14-30, 1972 period. Dr. G. T. Orlob's November 15, 1978 memorandum to the SDWA Board examined the hydraulic depression created by the export pumps and t e gradient toward the export pumps along various channels during this period. Table VII-2 and figure VII-5 are taken from pages 8 and 10 of that memorandum. Table VII-2 shows the drawdown of HHW indicated for various dates and export rates. The period of June 22-25 was used to develop figure VII-5. During this period only the CVP steady export pumping was being made. Figure VII-5 shows the difference between Bacon Island tide levels and Clifton ferry tide levels as a function of CVP export rates. The figure also indicates a high tide level depression at Clifton Court of 0.1 foot for each 1,000 ft^3/s of steady export pumping.

Data collected in 1977 was used by the DWR to compare two 15-day periods with markedly different export rates and with other pertinent conditions only moderately different (see table VII-3). The period October 17-31, 1977 included an average export of about 300 ft^3/s and a San Joaquin River flow at Vernalis of about 250 ft^3/s. The period December 17-31, 1977 included an average export rate of about 9,400 ft^3/s and a San Joaquin River flow at Vernalis of 470 to 600 ft^3/s. Table VII-4 compares the differences in the 15 day means of each tidal phase between the selected control station at Rock Slough and stations in the South Delta for the two periods. About 5,800 ft^3/s of this average export rate was by the SWP which diverted at high tide. Therefore, the differences in water level depression near Clifton Court was greatest during the high tidal phase. The comparison between the October and December

TABLE VII-2

EXAMPLE OF TIDAL ELEVATION DATA
FOR SOUTH DELTA – JUNE 1972

| Date | Export, ft^3/s | | HHW, feet MSL | | ΔH, feet |
	SWP	CVP	Bacon Island	Clifton Ferry	
6-16-72	2109	4191	2.79	1.67	-1.12
6-17-72	2090	4196	2.34	1.18	-1.16
6-18-72	2382	4204	2.81	1.56	-1.25
6-19-72	2331	4180	3.45	2.28	-1.17
6-20-72	2411	4233	3.42	2.22	-1.20
6-21-72[1]	2362	3561	3.39	1.85	-1.54
6-22-72	0	2558	2.93	2.51	-0.42
6-23-72	0	1173	3.46	3.25	-0.21
6-24-72	0	923	3.25	3.07	-0.18
6-25-72	0	926	3.45	3.28	-0.17
6-26-72	487	947	3.69	3.52	-0.17
6-27-72	911	968	3.68	3.37	-0.31
6-28-72	945	965	3.52	3.17	-0.35
6-29-72	1564	963	3.35	2.98	-0.37
6-30-72	1682	1041	2.98	2.34	-0.64
6-30-72	1682	1041	3.10	2.38	-0.72

[1] Andrus and Brannon Islands were filling due to a levee failure June 21 at about 0030. The effect on the tidal elevation at Bacon Island is indicated in figure VII-6, where a small depression in the water level curve is noted for about an hour following the break. It may be expected that this effect would have had only a minor influence in the water levels in the Southern Delta.

Figure VII-5   DEPRESSION IN HWL AT CLIFTON COURT RELATIVE TO MIDDLE RIVER
AT BACON ISLAND AS A RESULT OF CVP EXPORT PUMPING AT TRACY

TABLE VII-3

CLIFTON COURT FOREBAY

Daily Operation of Gates

Month October , 1977

DATE	TIME OPENED	TIME CLOSED	DAILY AMOUNT OF INFLOW IN ACRE-FEET
17			0
18	1010	1325	198
19	1800	1848	99
20	2000	2050	99
21	1311	1625	595
22	1733	2000	595
23			0
24			0
25	1041	1217	298
26			0
27			0
28	0842	1000	298
29	0855	0945	298
30	0853	1012	298
31	1015	1250	1,388

Month December , 19 77

DATE	TIME OPENED	TIME CLOSED	DAILY AMOUNT OF INFLOW IN ACRE-FEET
17	0016		13,231
18	0807	0430	
	2204	1845	10,468
19	0840	0617	
	2325	1836	10,168
20		2007	11,615
21	0005	2050	8,866
22	0015	0740	
	1120	1645	9,332
23	0723	1640	7,735
24	0219	0710	
	0910	1905	10,897
25	0300	2153	13,095
26	0330	2200	12,473
27	0330	2200	11,974
28	0445		11,931
29		0005	
	0517		12,083
30		0042	
	0530		11,362
31		0021	
	0555		10,963

TABLE VII-4

EXPORT EFFECTS ON TIDE STAGES[1]

		15 Day Mean Tidal Differences between Old River at Rock Slough and indicated locations	
		1977	
		Oct. 17-31	Dec. 17-31
Delta Tide Stations	Tidal Stage	296 ft^3/s [2]	9,368 ft^3/s [2]
	HH	0.10	0.55
	LH	0.10	0.49
	HL	0.16	0.41
1. Old River near Byron	LL	0.10	0.23
	HH	0.02	0.52
	LH	0.03	0.44
	HL	0.10	0.36
2. Middle River at Borden Hwy.	LL	0.06	0.18
	HH	0.04	1.08
	LH	0.06	0.95
	HL	0.17	0.47
3. Old River at Clifton Court Ferry	LL	0.09	0.32
	HH	0.12	1.04
	LH	0.12	0.88
	HL	-0.04	0.30
4. Grantline Canal at Tracy Road Bridge	LL	-0.30	-0.07
	HH	-0.13	0.55
	LH	-0.11	0.42
	HL	-0.31	0.00
5. Middle River at Mowry Bridge	LL	-0.67	-0.60
	HH	0.25	1.20
	LH	0.62	0.99
	HL	-0.55	0.08
6. Old River near Tracy Road Bridge	LL	-0.93	-0.61
	HH	0.13	1.05
	LH	0.13	0.88
	HL	-0.12	-0.30
7. Tom Paine Slough above Mouth	LL	-0.32	-0.13
	HH	0.02	0.57
	LH	-0.10	0.37
	HL	-0.18	-0.42
8. San Joaquin River at Mossdale	LL	-1.35	-1.01

[1] Range of San Joaquin River flows near Vernalis was 232-268 ft^3/s and 470-600 ft^3/s during the Oct 17-31 period, and the Dec 17-31 period, respectively.

[2] Tracy Pumping Plant and Clifton Court Intake combined 15 day mean diversion rate.

periods demonstrates, in general, that reductions in 15 day average water levels due to an increase in export as measured in the prototype are of the same order as those obtained in mathematical model studies to be discussed later in the text. The reduction in 15 day average water level at high tide at Clifton Court is a composite effect of high tide diversion into Clifton Court Forebay and steady diversion into the Delta-Mendota Canal. The impact of steady pumping is estimated to be about an average of 0.08 foot depression at Clifton Court Ferry per 1,000 ft^3/s based on the analysis of the 1977 data. The impact of intermittent diversion into Clifton Court Forebay at high tide is approximately 0.14 foot per 1,000 ft^3/s of average daily diversion. The combined effect of steady and intermittent pumping was to depress the high tide level by about 1.1 feet. Table VII-5 discusses the data and describes the procedures used to calculate these estimates.

The above tests showed that water level drawdown was about the same in Old River near Tracy Road and at Clifton Court. A depression in water level was evident as far away as Mossdale. However, an exact effect at Mossdale cannot be determined by tests in which San Joaquin River flows and agricultural diversions upstream from the export pumps vary between test periods. For example, in December 1977 the San Joaquin River flow was two to three times greater, and the agricultural diversions were presumably less than in October 1977.

A graphic presentation of the effect of intermittent export pumping on water levels at high tide is shown in figure VII-6. This figure shows the tide levels during the upper portion of the tide at Clifton Court and at Old River at Tracy Road on June 20-21, 1972, and compares them to the Bacon Island tide level. During this period, the average daily export rates were 2,362 ft^3/s

Table VII-5. Impact of CVP and SWP export on
water levels in Old River at Clifton Court Forebay[1]

Observation period	CVP-SWP mean daily diversion rate in ft^3/s		Mean 15-day tidal elevation difference between Old River at Rock Slough and Clifton Court Forebay in feet			
	CVP	SWP	HH	LH	HL	LL
October 17-31, 1977	180	140	0.04	0.06	0.17	0.09
December 17-31, 1977	3,600	5,800	1.08	0.95	0.47	0.32
Differential	3,420	5,660	1.04	0.89	0.30	0.23

Steady pumping impact = $\dfrac{\dfrac{\text{HL Diff.} + \text{LL Diff.}}{2}}{\text{average DMC Diversion in 1,000 } ft^3/s}$

$= \dfrac{\dfrac{0.30 + 0.23}{2}}{3.42}$ $= 0.08 \text{ ft}/1,000 \text{ } ft^3/s$

Intermittent pumping impact = $\dfrac{\text{HH Diff.- steady pumping impact}}{\text{average daily diversion to CCFB in 1,000 } ft^3/s}$

$= \dfrac{1.04 - \dfrac{0.08 \times 3,420}{1,000}}{5.66}$ $= 0.14 \text{ ft per 1,000 } ft^3/s$ of average daily diversion

Intermittent pumping impact = $\dfrac{\text{HH} - \text{Steady pumping impact}}{\text{Average daily diversion to CCFB} \times \dfrac{24 \text{ hours}}{\text{Diversion period}}}$

$= \text{feet per 1,000 } ft^3/s \text{ of intermittent diversion.}$

$= \dfrac{1.04 - 0.08 \times 3.42}{5.66 \times \dfrac{24}{17}} = \dfrac{1.04 - 0.27}{7.99} = 0.096 \text{ or } 0.10 \text{ feet per 1,000 } ft^3/s$

Total impact at high high tide = $0.08 \times 3.42 + 0.14 \times 5.66 = 0.27 + 0.79$

$= 1.06$ feet as compared to the measured value of 1.04 feet.

---

[1]The rates of impacts identified in this analysis are approximations only.

Figure VII-6   WATER LEVELS IN SOUTHERN DELTA, 20-21 JUNE 1972

CVP Export = 4233 cfs   SWP Export (Avg) = 2411 cfs

for the SWP and 3,561 ft^3/s for the CVP. The southern Delta tide levels
would probably have been about the same height as the Bacon Island tide in the
absence of pumping. Using the indicated difference between HH water at Bacon
Island and Clifton Court as the effect of pumping and the procedure outined in
table VII-5, it is estimated that the intermittent pumping impact was about 0.5
feet per 1,000 ft^3/s of average daily diversion and 0.122 feet per 1,000 ft^3/s
of actual intermittent diversion rate. The total impact was a reduction in
water level at high tide of about 1.5 feet, extending as far upstream on Old
River to Tom Paine Slough.

The comparison of the impact of intermittent pumping rates on the
water levels near Clifton Court in feet per 1,000 ft^3/s of average daily
diversion is appropriate when the periods of diversion are approximately the
same. Comparing the impact of intermittent pumping during the June 20-21, 1972
period with the October 17-31, 1977 and December 17-31, 1977 periods, in feet
per 1,000 ft^3/s of average daily diversion will give a distorted result.
During the 1972 period the actual diversion of 10,300 ft^3/s occurred over a
period of 5.5 hours whereas during the 1977 period the actual diversion of
7,990 ft^3/s was sustained for 17 hours. The maximum pumping water level
drawdown on June 21, 1972, between Bacon Island and Clifton Court was 1.26'
feet; during the 1977 period between Rock Slough and Clifton Court the drawdown
was 0.77 foot. Expressing these drawdowns in terms of actual rates of diver-
sion for each period results in 0.122 foot per 1,000 ft^3/s and 0.10 foot
per 1,000 ft^3/s, respectively.

The impact of export pumping on water levels in the vicinity of Clifton
Court Forebay is relatively insensitive to the flows in the San Joaquin River

at Vernalis. However, the effects of export pumping on the hydraulic gradient between Clifton Court Ferry and the San Joaquin River does vary with the riverflows. The project impact on net flow rates and water levels in this reach are greatest at low rates of inflow.

A mathematic procedure (Hardy Cross network analysis) was used to describe the relationship between head loss within individual channels and the average exports and flows in the San Joaquin River. A memorandum dated February 16, 1951, summarized the network analyses of the Lower Sacramento-San Joaquin Delta that were made in connection with the design of the Delta Cross Channel. Copy of this memorandum is included in Appendix 4. A simplified technique, based on the assumption of steady flow with no tidal fluctuation was used to demonstrate the effect of San Joaquin River inflow on the distribution of drawdown related to a constant export. This procedure assumes no agriculture diversion within the southern Delta. (During periods of low flow this is seldom a realistic assumption.)

For the semi-quantitative use the various channels were combined into four equivalent channels as shown. The ship channel because of its relatively large cross-section was assumed to act as a manifold at a constant level. The resistance values represent channel resistance coefficients such that head loss (h) = 5.543 x 10^{-8} rQ^2 where the constant was derived from the Manning equation.

Flow distributions were developed: Case A with 4,600 ft^3/s export and a downstream flow at Mossdale of 1,000 ft^3/s, and Case B with the same export (4,600 ft^3/s), but a downstream flow of 300 ft^3/s.

Case A

Q_1 in channel 1 = 3,550 ft^3/s

Q_2 in channel 2 = 50 ft^3/s

Q_3 in channel 3 = 1,050 ft^3/s

$\Delta h_1 = 0.145$, $\Delta h_2 = 0.00014$

and $\Delta h_3 = 0.1405$

Manifold *(Ship channel)*

3550 ft 3/s
$r_1 = 0.204$
①
② 50 ft 3/s $r_2 = 10$
DMC 1050 ft 3/s ③
4600 ft 3/s $r_3 = 2.3$ 1000 ft 3/s

The junction of channel 2 and 3 which represents Mossdale approximately is subject to negligible drawdown (1 percent of drawdown at Tracy).

Case B

$Q_1 = 3,870$ ft^3/s

$Q_2 = 430$ ft^3/s

$Q_3 = 730$ ft^3/s

$\Delta h_1 = 0.169$, $\Delta h_2 = 0.102$

and $h_3 = 0.068$

Manifold *(Ship channel)*

3870 ft 3/s
$r_1 = 0.204$
①
② 430 ft 3/s $r_2 = 10$
DMC 730 ft 3/s ③
4600 ft 3/s $r_3 = 2.3$ 300 ft 3/s

At Mossdale the drawdown (Δh_2) is 0.102 or 60 percent of the drawdown at the DMC intake.

The analysis indicated that when the flows at Mossdale are less than 500 ft^3/s and the pumping is approximately 4,600 ft^3/s, the gradient between the pumps and the bifurcation was very flat. Therefore, depression of the water levels at Clifton Court would be felt as far away as the bifurcation and even upstream beyond Mossdale. However, with riverflows at Mossdale of a magnitude of about 1,000 ft^3/s, the gradient is much steeper and, therefore, the pumping impact is less at the bifurcation.

Model studies--Tests such as those just described in 1968 and 1977 are difficult to arrange. They are, therefore, limited in the range of condi-

tions tested. Furthermore, conditions of tide, riverflow, and agricultural diversions vary during the tests, thereby modifying results, particularly for points far upstream of the export pumps. Therefore, it was necessary to develop a mathematical model in order to examine a wider range of conditions and to avoid the uncertainties of test data wherein conditions other than export rates vary during the tests. A mathematical model for this purpose was developed for SDWA by Dr. G. T. Orlob per his report entitled "Investigation of Water Level Problems in the Southern Delta - Model Studies" and dated May 14, 1979. The model is a refinement of an earlier Delta-wide model which was developed under Dr. Orlob's direction and commonly referred to as the WRE model.

It was first necessary to establish a reference station for southern Delta tides. Delta tides do not correlate reliably with ocean tides for various reasons. (See DWR-USBR report dated September 1970 and titled "Sacramento--San Joaquin River Delta Low Tides of April--May 1970.") The Bacon Island tide station was, therefore, chosen as being reliably related to the southern Delta tide levels which would occur in the absence of all pumping.

The model was calibrated so as to obtain a close a match as possible between model results and the measured data from southern Delta tide gages during various conditions of tide, export diversion, and riverflow. Comparison of the model's predictions and actual tidal curves for conditions of steady diversion indicate that the model is a useful tool for water level studies. The model still requires verification for some special cases . However it improves understanding of the interrelationships between water level changes and export pumping under the dynamic conditions induced by tides in the southern Delta.

Table VII-6 shows the model's predicted change in water level due to export pumping at various southern Delta points and for various export rates. With a CVP export rate of 4,323 ft^3/s and no SWP export and a 550 ft^3/s riverflow rate at Vernalis, the drawdown of water levels by the export pumps is calculated to be 0.52 foot at HHW and 0.40 foot at LLW at the CVP intake channel; 0.51 at HHW and 0.47 at LLW at the Westside Irrigation District intake channel on Old River; 0.41 foot at HHW and 0.37 foot at LLW at Old River and Tom Paine Slough; 0.35 foot at HHW and 0.31 foot at LLW at Old River and Middle River; and 0.34 foot at HHW and 0.13 at LLW at Mossdale. Steady pumping impacts predicted by the mathematical model presented in table VII-6 is compared to the LLW value calculated using the 1968 pumping test rated of depression presented on table VII-1.

	Model Run	May 1968 Test[1,2] Results
Old River at Clifton Court Ferry	-.40	-.30
Old River at Tracy Road	-.39	-.27
Grant Line at Tracy Road	-.44	-.27
Tom Paine Slough	-.37	-.27
San Joaquin River at Mossdale	-.13	-.13

[1] The May 1968 test results were adjusted to reflect the same rate of diversion as simulated in the model run, i.e., the 1968 test results were multiplied by the factor of $\frac{4,323}{4,775} = 0.90$.

[2] During the 1968 test 10 to 31 percent of the flows diverted from the Delta by the SWP were withdrawn from Italian Slough not Clifton Court Forebay as simulated in the model study.

With the same CVP export rate and the same riverflow rate at Vernalis, but with a 4,800 ft^3/s average daily SWP export rate (drawn off the high

TABLE VII-6

SUMMARY OF WATER LEVEL CHANGES IN THE SOUTHERN DELTA
DUE TO EXPORT PUMPING BY THE CVP AND SWP[1]

Node	Location	RUN SD-29A $Q_e{}^{[2]}$(DMC) = 4323 Q_e(SWP) = 0			RUN SD-29B Q_e(DMC) = 4323 Q_e(SWP) = 1600 $Q_{ep}{}^{[3]}$(SWP) = 2000			RUN SD-30 Q_e(DMC) = 4323 Q_e(SWP) = 2800 Q_{ep}(SWP) = 7000			RUN SD-32 Q_e(DMC) = 4323 Q_e(SWP) = 4800 Q_{ep}(SWP) = 12,000		
		HHW	HTL	LLW	HHW	HTL	LLW	HHW	HTL	LLW	HHW	HTL	LLW
1	Bacon Isl. (Input)	0	0	0	0	0	0	0	0	0	0	0	0
20	Clifton Ct.	-0.36	-0.35	-0.34	-0.89	-0.47	-0.36	-1.08	-0.58	-0.34	-1.74	-0.77	-0.26
22	Old R. @ DMC	-0.52	-0.49	-0.40	-1.01	-0.59	-0.40	-1.17	-0.70	-0.39	-1.83	-0.89	-0.32
26	HSID	-0.51	-0.47	-0.47	-1.01	-0.58	-0.49	-1.17	-0.68	-0.46	-1.84	-0.87	-0.38
32	Old R. @ Tracy Rd.	-0.43	-0.43	-0.39	-0.97	-0.54	-0.40	-1.12	-0.64	-0.37	-1.81	-0.83	-0.29
115	Grantline @ Tracy Rd.	-0.44	-0.40	-0.44	-0.93	-0.60	-0.46	-1.09	-0.61	-0.43	-1.76	-0.80	-0.36
34	Tom Paine Sl.	-0.41	-0.42	-0.37	-0.92	-0.53	-0.40	-1.11	-0.62	-0.39	-1.78	-0.81	-0.34
35	Salmon Sl.	-0.40	-0.39	-0.33	-0.90	-0.50	-0.37	-1.06	-0.59	-0.36	-1.73	-0.79	-0.31
39	Old R. @ Middle R.	-0.35	-0.33	-0.31	-0.81	-0.46	-0.35	-1.00	-0.56	-0.34	-1.63	-0.74	-0.31
44	Old R. @ San Joaquin	-0.31	-0.27	-0.18	-0.65	-0.38	-0.24	-0.89	-0.46	-0.26	-1.32	-0.61	-0.29
139	San Joaquin @ Mossdale	-0.34	-0.26	-0.13	-0.66	-0.38	-0.22	-0.87	-0.46	-0.27	-1.33	-0.65	-0.37

[1] Based on mathematical model analysis using a version of the WRE Model
[2] Q_e is the average daily diversion
[3] Q_{ep} is the actual diversion during HHW
Note: Vernalis flow rate 550 cfs.

tide at about 12,000 ft^3/s), the drawdown at the CVP intake channel is increased to 1.83 feet at HHW and 0.32 foot at LLW; at Old River and Tom Paine Slough it is 1.78 feet at HHW and 0.34 foot at LLW; and at Mossdale it is 1.33 feet at HHW and 0.37 foot at LLW. The intermittent pumping impact at Clifton Court was calculated at 0.127 foot per 1,000 ft^3/s at HHW, which compares favorably with the rate calculated using the June 21-22, 1972 data (0.122 ft/1,000 ft^3/s).

Impact of Export Pumping and Channel Configuration on Water Circulation and Water Quality

Circulation of water in southern Delta channels and the related water quality in those channels is influenced by tidal activity, export and local pumping, inflow and channel configuration. Tidal activity is the dominant factor ᴗ ᵀˡuencing circulation for short time periods. For longer periods, net flow direction ᴗ ᵈ primarily by export pumping and inflows becomes the major influence. The circulation is determined by the excursion and the volume of displacement duri idal cycle, which are related to the tidal prism upstream from any given su taken together with the cross sectional area at that station. Values of exc from a low slack to a high slack tide range to as much as 3 miles in the sᴗ ᐟ Delta.

Net flow direction is markedly changed by vᴗ physical works such as pumps, siphons, and tidal gates. Circulation chanᵧ s have been studied in the field and by models, both physical and mathematical. A relationship between the division of flow at the head of Old River and export pumping has been developed per figure VII-7. This figure is a modification of plate 11 of the appendix to DWR Bulletin 76. This plot depicts the flow split at the

RATIO OF DELTA-MENDOTA CANAL PUMPING TO FLOW IN SAN JOAQUIN RIVER AT MOSSDALE

RATIO OF FLOWS IN SAN JOAQUIN RIVER AT BRANDT BRIDGE TO FLOWS IN
SAN JOAQUIN RIVER AT MOSSDALE

NOTE: Flows in northwesterly direction in San Joaquin
        River at Brant Bridge positive and in opposite
        direction negative.

This is plate 11 from the California Department of
Water Resources' Report entitled Salinity Incursion
and Water Resources Bulletin No. 76 Appendix on
Delta Water Facilities dated April 1962.

RATIO OF FLOW AT TWO LOCATIONS
ON SAN JOAQUIN RIVER AS INFLUENCED
BY DELTA-MENDOTA CANAL PUMPING
APRIL 1962

bifurcation of Old River and the San Joaquin River in relationship to the rate of export pumping. This determination of the relationship is an approximation because it does not account for the seasonally varying channel depletions between Vernalis and the head of Old River and because net flows are difficult to determine in tidal channels. However, the approximation is useful in analyses of the circulation and water quality. Depending upon the rate of export and local pumping, varying percentages of the San Joaquin inflow are drawn toward the export pumps even to the extent of reversing the normal downstream flow of the San Joaquin River below its bifurcation with Old River.

The induced flow toward the export pumps is carried mainly by Salmon Slough and Grant Line and Fabian Canals. Downstream flows in Middle River and Old River west of Salmon Slough have serious impediments to flow in the form of width and/or depth constrictions as previously discussed. These limitations are exacerbated to some degree by the lowering of water levels at the entrance of these channels.

Hydraulic restrictions in Middle River and portions of Old River tend to limit circulation and increase the likelihood of stagnation and poor water quality. These conditions may be aggravated further by reductions in water level, depth and/or tidal prism. Such occurrences are illustrated by the behavior of Old River between Salmon Slough and the DMC intake channel during July 1976, as shown in figure VII-8. The average monthly TDS concentration in Old River between Salmon Slough and the Westside Irrigation District intake generally exceeded 1,000 mg/L, while at the DMC intake the TDS averaged 312 mg/L. The rather large gradient of TDS between these two locations indicates that the effects of tidal mixing, and any available advective flow is not

Figure VII-8 TOTAL DISSOLVED SOLIDS IN THE SOUTH DELTA CHANNELS*
JULY 1976

Sources: WPRS continuous EC recorders, grab samples by Westside Irrigation
District, Reclaimed Islands Land Co., Piscadero Reclamation District
and Nelson Laboratories.

*Where ranges are indicated, they represent extreme values of daily observation
or continuous records during the month. Where no range is indicated, data
correspond to a very small number of samples.

sufficient to offset the effect of salt accumulation in this channel. Such circulation as did exist may have been aided by the Westside Irrigation District diversion since there are no other significant diversions between the district's intake and the DMC intake.

The operation of the export pumps draws water from all contributing channels, including the Old River--Salmon Slough--Grantline Canal principal channel through which water from the San Joaquin River enters the zone affected by export. Data derived from the Service's continuous EC monitors show that at low tide following a downstream tidal excursion the EC near Clifton Court is generally higher than at high tide when cross Delta flows from the Sacramento River are most likely to be dominant. As an illustration the quality of water in San Joaquin River at Vernalis between July 9 and July 18, 1978, averaged about 635 umhos EC with no tidal variation whereas the quality in the Delta-Mendota Canal intake channel varied about threefold between the high and low tidal stages. The 10-day average qualities in each tidal phase in umhos at the various tidal phases between July 9 through July 18, 1978 were as follows:

Tidal phase	Water quality (micromhos)
HH	323
LH	212
LL	631
HL	385

SUMMARY AND CONCLUSIONS

CHANNEL DEPTHS AND CROSS SECTIONS

Changes in channel geometry were assessed by comparison of surveys
made in 1913 and 1965 by the Corp of Engineers and in 1933-34 by the United
States Coast and Geodetic Survey and at various times during the period 1957
through 1976 by the Department of Water Resources. Results of the analysis for
each principal channel is summarized below:

San Joaquin River--Vernalis to Mossdale Bridge

The bottom elevation increased from 0.5 to 9.5 feet, with an average
increase of about 4 feet. This aggradation raised the bottom elevation of
about 45 percent of this reach to an elevation of 1.5 to 3.5 feet above LWD
whereas it was 2 to 7 feet below LWD in 1933. This probably has occurred
due to reduced floodflows, a normal supply of river sediment load, and the fact
that this reach is where the river enters the tidal zone. Sediments tend to
deposit at the entry to a tidal zone.

Old River--San Joaquin River to Salmon Slough

The bottom elevation dropped an average of 4 feet, i.e., the channel
degraded. This degradation is unexplained.

Grant Line and Fabian Canals

These channels degraded between 1957 and 1973 by an average of 4 feet.
This period corresponds to an increase in Delta export pumping. Channel
degradation could have been due to maintenance dredging of the channels performed
by the local reclamation districts and the Corps of Engineers.

Middle River--Old River to Victoria Canal

This channel has aggraded since the 1933 survey from an average maximum

bottom elevation of 6 feet below LWD to an average maximum bottom elevation of

4 feet below LWD. About 55 percent of the reach, that immediately north of

Old River, has aggraded an average of 0.5 foot since 1933-34. The most restric-

tive section is now about 0.5 foot below LWD as compared to the previous

1 foot below LWD. The channel conveyance capacity is quite low and often less

than the agricultural diversion rate. There is no evidence of recent channel

maintenance dredging (access to 55 percent of the most restrictive sections is

hampered by two fixed span bridges).

Old River--Salmon Slough to DMC Intake Channel

This channel also has restrictive cross sections with maximum depths

of about 3.5 feet below LWD and a minimum mean depth of about 2 feet below LWD.

There has been little change since the 1933-34 survey.

Changes in channel cross sections that have been observed since 1933-34

are a consequence of modifications in the hydraulic regimen of the southern

Delta: export pumping by the CVP initiated in 1951, intermittent diversions by

the SWP commencing in 1968, and reduced San Joaquin River inflows at Vernalis.

The analysis of channel depths within the South Delta Water Agency does not

establish whether or not export pumping has caused appreciable siltation or

scour within the SDWA channels. Channel degradation in the reach of Old River

between Salmon Slough and the San Joaquin River is unexplainable. The channel

degradation within Grant Line--Fabian Canals could be attributed to export

pumping and/or dredging. This channel carries the largest proportion of San

Joaquin River flows which are drawn to the export pumps. The decrease in

channel resistance in this channel modifies the proportion of flows carried by this channel and the proportion carried by the reach of Old River between Salmon Slough and the export pumps.

The control of siltation in some South Delta channels requires periodic channel maintenance. No routine channel maintenance program exists in this area of the Delta at this time.

IMPACT OF EXPORT PUMPS ON WATER LEVELS

Steady diversion of flows by the CVP reduces the water level at Clifton Court and adjacent channels by a range of 0.07 to 0.10 foot per 1,000 ft^3/s, or about 0.32 to 0.46 foot at full capacity of 4,600 ft^3/s. This impact influences the water levels in Old River and Grant Line Canal upsteam to Salmon Slough, at about the same magnitude, thereby directly impacting the entrance to Tom Paine Slough, which relies on tidal elevation differences to produce the gradient for flow into the Slough.

The intermittent diversions into Clifton Court Forebay by the SWP reduce the HHW levels by about 0.10 to 0.127 per 1,000 ft^3/s of water diverted. At full capacity of the CVP, operating at 4,600 ft^3/s on a steady basis, and the SWP, operating only on the high tide, with a 10,000 ft^3/s diversion rate,[1] the water level depression at HHT may be expected to be in the range of 1.34 to 1.76 feet.

Reductions in water level also are evident at Mossdale Bridge on the San Joaquin River. However, the water level depression at this point is related to the portion of the inflow from the San Joaquin River which reaches

---

[1] The maximum SWP pumping rate of 6,000 ft^3/s into the aqueduct corresponding to this 10,000 ft^3/s high tide diversion to Clifton Court Forebay over a period of approximately 14 hours.

the bifurcation with Old River. When the riverflows at the bifurcation are less than 1,000 ft^3/s, the gradient between the pumps and the bifurcation flattens and the pumping effect is increased whereas at 1,000 ft^3/s the effect is relatively insignificant.

IMPACT OF EXPORT PUMPING ON WATER CIRCULATION AND QUALITY

During most summer periods, the San Joaquin River flows are now less than the net rate of channel depletion within the SDWA. The induced flow toward the export pumps which is caused by the drawdown of levels, is carried mainly by Salmon Slough and Grant Line and Fabian Canals. Downstream advective flows into the reach of Middle River between Old River and Victoria Canal and in the reach of Old River west of Tom Paine Slough are generally less than the agricultural diversions from those channels during dry seasons, thereby causing water to flow into these reaches from both ends permitting accumulation of salts from local return flows as illustrated in figure VII-8. Both of these channels have serious impediments to flow in the form of width and/or depth constrictions as previously discussed. However, it is apparent that substantial portions of low summer San Joaquin River flows pass through the upstream end of Old River and Grant Line and Fabian Canals and are diverted with the export.

The increase in net unidirectional flow from the San Joaquin River toward the pumps reduces the accumulation of drainage salts in the upper end of Old River and in Grant Line and Fabian Canals. However, the drawdown which causes this increase in flow does not necessarily induce net daily unidirectional flows through Middle River in the southern Delta, or in Old River from Tom Paine Slough west toward the DMC intake channel as discussed above.

177

Tidal circulation is reduced by the lowering of water levels. However tidal exchange of salts is dependent both on circulation and the difference in salt concentration between any two points in a channel. For example in the restricted reach of Old River even with the reduced tidal prism in the vicinity of the DMC intake channel, there is some flushing resulting from tidal exchange with better quality of water available.

Quality in dead end sloughs such as Paradise Cut and Old Oxbows rely e irely on tidal exchange. When San Joaquin River flows at Vernalis are less ᴗ ᴖ ᴛhe agricultural diversions south of Mossdale, the reach of San Joaquin Rive. ᴖnnel south of the bifurcation of Old River functions also functions like a b. ⁻lough and tidal flushing becomes important for water quality as well as for ᵗepth in that reach of channel.

The overall ᴛ ᴎf export pumping on the South Delta channels includes:

1. Reduction in ᴛ ⁻ᴛaulic capacity of channels with consequent reduced water availability ᴄ ᴖ local diversion points.

2. Increase in gradient toᴠ ᵗhe Delta export pumps which results in increased downstream advecᴛ..ᵥᴎ circulation from the San Joaquin River through the east end of Old River to Cᴵ Court via Grant Line Canal.

3. Availability of Sacramento River ᴡ. ⁻ the northern boundary of the southern Delta which is drawn into portions ᴖ ᴎe southern Delta channels through tidal mixing.

4. Increase in suction lift required of pumps of local diverters.

5. Increase in frequency of loss of prime (due to inadequate water depth) by pumps of local diverters.

6. Reduction in tidal prism with resultant decrease of tidal flows and of tidal flushing of salts, particularly in shallow, or stagnant, or blind channels.

This report does not attempt to quantify all of these export pump impacts or to determine the water levels, hydraulic capacities, and salinity levels needed in southern Delta channels. Water level drawdown, of the magnitude indicated, obviously has an impact on water availability in the shallowest channels, but determining the net effect on salinity due to changes in advective and tidal flow would require additional study of the net effect in each channel. Furthermore, the impact of export pumping also varies with the degree to which San Joaquin River flow and salinity at Vernalis are altered.

APPENDIX 1

MONTHLY FLOW DATA (KAF) AND

MONTHLY CHLORIDE DATA (P/M)

THIS IS THE DATA FILE OF ACTUAL SAN JOAQUIN RIVER FLOWS (KAF) AT VERNALIS.

		OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	VN	86.70	73.20	79.30	111.00	94.40	151.00	154.00	136.00	164.00	76.20	56.60	85.10
1931	VN	103.00	97.60	117.00	95.30	88.90	54.20	23.10	27.30	23.30	14.30	14.00	19.00
1932	VN	29.40	38.30	76.90	205.00	621.00	301.00	286.00	713.00	898.00	356.00	71.30	63.70
1933	VN	103.00	113.00	115.00	124.00	167.00	107.00	68.40	84.80	316.00	68.20	41.00	68.40
1934	VN	94.10	91.00	148.00	169.00	124.00	105.00	41.80	39.30	37.30	24.30	23.60	29.80
1935	VN	52.20	76.80	98.80	223.70	196.30	250.60	878.20	1007.00	938.80	165.90	61.20	80.30
1936	VN	125.10	115.40	155.90	203.20	688.00	878.10	773.10	1020.00	661.60	187.40	69.00	76.20
1937	VN	116.20	116.60	175.60	202.40	688.30	812.20	860.60	1233.00	925.70	200.50	69.40	83.10
1938	VN	116.70	117.80	326.40	381.20	1301.00	2100.00	1333.00	1743.00	2181.00	898.30	206.60	132.40
1939	VN	163.90	226.00	227.50	251.50	231.60	124.60	146.80	125.30	59.00	46.50	44.00	61.50
1940	VN	91.30	85.40	97.60	254.00	493.10	902.30	965.20	879.30	645.60	122.70	72.90	100.40
1941	VN	98.60	102.00	185.20	438.60	727.90	1302.00	1017.00	1309.00	1327.00	562.10	128.80	100.30
1942	VN	135.20	138.60	293.70	518.40	706.90	533.40	798.20	1017.00	1323.00	478.20	103.60	114.00
1943	VN	137.50	138.80	268.40	347.20	725.80	1422.00	1075.00	920.60	693.40	135.80	94.80	100.50
1944	VN	129.60	116.20	146.80	165.40	164.60	294.70	136.90	235.30	201.40	76.60	67.10	71.40
1945	VN	101.40	147.20	232.90	237.60	604.30	566.70	534.80	855.60	673.80	238.60	109.40	120.90
1946	VN	169.60	207.30	352.50	584.80	330.70	229.60	357.90	802.90	344.10	90.10	75.30	88.30
1947	VN	111.60	155.70	222.40	171.10	133.70	138.90	88.50	125.80	56.10	32.40	35.00	63.90
1948	VN	80.80	105.50	104.20	85.10	47.50	36.80	82.90	307.50	512.10	81.70	44.60	64.70
1949	VN	95.20	88.80	91.40	107.00	78.60	213.30	122.40	217.00	119.20	34.60	37.00	42.50
1950	VN	77.90	94.10	96.60	122.90	196.70	135.60	319.30	308.20	298.30	42.30	38.20	56.30
1951	VN	81.40	482.10	1545.00	632.10	600.50	477.70	157.80	401.20	198.60	53.50	46.70	61.60
1952	VN	109.70	104.90	192.80	544.20	661.90	845.30	1202.00	1699.00	1389.00	215.10	83.30	96.40
1953	VN	114.70	129.50	225.00	365.70	204.00	71.50	90.40	188.10	292.40	98.60	46.00	65.00
1954	VN	100.20	98.90	108.30	101.90	131.00	274.30	301.00	412.90	76.50	33.30	33.60	44.90
1955	VN	32.30	82.50	111.50	182.30	136.10	96.00	54.60	70.70	89.00	25.60	26.50	36.30
1956	VN	49.20	63.70	670.60	1663.00	993.90	460.30	372.60	859.30	729.00	214.20	116.90	112.20
1957	VN	122.90	131.60	154.00	118.10	97.90	187.80	78.90	158.70	223.70	53.80	46.30	68.30
1958	VN	126.40	133.80	153.30	148.80	301.80	743.60	1661.00	1379.00	929.30	251.60	94.40	133.40
1959	VN	174.30	216.10	181.70	143.40	181.50	127.20	48.30	48.60	31.70	19.20	24.70	46.70
1960	VN	53.90	62.60	72.80	85.80	99.10	36.60	30.80	38.00	17.40	13.70	16.50	22.90
1961	VN	43.80	60.30	79.10	82.30	62.10	27.30	11.90	23.40	12.30	6.40	9.30	19.10
1962	VN	25.20	35.30	43.80	49.50	320.90	364.80	124.10	161.20	208.10	52.60	42.70	59.10
1963	VN	89.40	97.80	149.70	107.80	454.60	160.30	512.70	574.20	396.50	112.00	67.40	90.20
1964	VN	164.60	179.80	217.20	176.60	97.60	57.10	45.50	43.20	38.70	23.60	27.10	53.50
1965	VN	86.90	140.20	371.20	894.80	440.30	327.50	596.70	325.60	336.20	121.30	75.10	99.90
1966	VN	181.00	216.80	383.80	323.90	227.20	117.70	58.40	53.10	33.90	27.00	30.70	43.20
1967	VN	61.70	79.10	269.00	197.30	353.40	401.90	862.50	1252.00	1190.00	642.50	124.20	120.70
1968	VN	167.60	206.70	223.50	180.80	150.50	190.20	85.40	54.90	35.20	30.90	41.20	55.80
1969	VN	85.10	95.50	155.70	849.40	1808.00	1898.00	1316.00	1513.00	1659.00	356.80	142.90	193.70
1970	VN	274.40	275.40	246.70	683.50	510.50	441.50	99.53	147.20	160.00	81.70	64.22	78.51

THIS IS THE DATA FILE FOR STANISLAUS RIVER FLOW AT RIPON.

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1931 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1932 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1933 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1934 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1935 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1936 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1937 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1938 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1939 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1940 RP	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
1941 RP	15.19	18.40	28.29	52.11	72.00	186.10	178.90	386.50	173.90	36.34	14.73	13.63
1942 RP	15.46	27.82	53.31	77.20	175.90	71.01	215.00	294.30	232.10	56.69	13.33	14.70
1943 RP	16.51	27.44	52.74	113.80	122.20	313.20	265.30	203.30	108.20	17.13	14.71	13.87
1944 RP	16.51	17.46	26.32	31.60	17.42	81.66	31.01	104.40	51.71	14.11	11.97	11.69
1945 RP	13.40	31.88	60.44	55.84	105.40	111.40	125.80	265.20	152.00	25.57	14.42	13.41
1946 RP	16.30	30.36	74.98	146.90	50.39	64.93	155.20	234.30	61.95	15.50	13.59	12.54
1947 RP	11.83	21.40	38.42	11.56	11.15	37.56	52.60	82.53	15.35	9.70	9.37	9.59
1948 RP	10.72	16.19	25.94	17.35	12.07	10.46	53.08	216.70	180.30	21.01	10.90	9.76
1949 RP	12.14	14.62	14.11	24.34	12.62	68.69	44.82	158.70	52.26	10.85	9.86	9.80
1950 RP	11.78	11.38	13.60	37.55	53.77	42.70	152.40	235.50	112.30	13.36	11.36	10.38
1951 RP	11.39	268.90	467.40	152.90	122.10	127.60	81.59	130.90	38.28	13.55	11.01	10.18
1952 RP	23.12	21.25	54.38	78.75	116.60	155.00	224.90	473.60	294.80	57.17	15.56	14.01
1953 RP	15.91	20.93	35.03	84.12	39.03	12.43	56.38	109.50	153.60	30.36	12.19	11.73
1954 RP	15.30	21.20	21.35	13.62	22.92	70.90	146.00	147.50	13.96	9.62	9.99	8.93
1955 RP	11.97	15.36	33.63	47.53	28.22	35.62	13.14	37.40	63.93	8.67	7.98	7.14
1956 RP	8.32	9.77	275.70	317.50	117.40	80.34	147.90	312.30	187.90	62.18	12.01	10.71
1957 RP	23.82	27.18	21.32	17.86	7.96	30.62	11.10	73.48	81.53	12.04	10.30	10.69
1958 RP	14.07	10.43	10.46	32.43	78.41	136.90	242.80	362.20	217.00	36.62	18.55	20.04
1959 RP	19.91	29.56	49.61	28.05	23.29	38.99	9.97	9.16	7.85	6.98	7.96	9.71
1960 RP	9.17	8.69	9.00	8.24	9.70	6.83	7.21	8.64	6.66	5.96	6.09	6.10
1961 RP	7.65	9.66	11.02	11.18	8.71	6.50	5.58	5.38	3.84	3.15	3.74	4.56
1962 RP	5.61	6.34	6.87	6.63	54.76	70.77	49.61	73.72	103.40	11.44	8.73	9.24
1963 RP	13.48	14.84	19.22	11.40	133.50	42.46	177.80	288.80	118.10	16.34	11.24	13.74
1964 RP	24.04	17.54	32.15	54.94	24.78	12.03	10.23	8.16	7.15	6.37	6.53	7.98
1965 RP	9.99	13.12	189.30	254.40	109.30	102.40	202.00	131.20	124.20	25.84	13.72	16.75
1966 RP	24.47	47.96	86.83	90.41	65.17	16.00	11.39	9.95	7.82	6.11	5.54	6.07
1967 RP	8.26	9.35	60.27	70.59	97.84	137.00	225.40	267.20	329.10	107.20	19.36	23.00
1968 RP	29.79	36.09	52.79	38.72	15.90	28.53	28.00	9.38	7.68	6.29	7.01	7.44
1969 RP	11.59	11.70	13.34	309.90	266.70	225.70	187.10	359.40	233.60	41.12	17.09	29.64

END OF FILE

1nh

THIS IS THE DATA FILE FOR THE ACTUAL FLOW AT MAZE ROAD BRIDGE (KAF).

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1931	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1932	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1933	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1934	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1935	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1936	0.00	0.00	0.00	162.20	564.30	668.20	574.60	767.60	503.80	150.60	55.10	64.10
1937	102.50	106.60	161.00	176.70	617.40	722.80	708.90	970.30	818.80	177.60	52.30	71.80
1938	110.50	100.80	0.00	341.20	1268.00	2077.00	1092.00	1265.00	1798.00	776.40	185.20	123.00
1939	140.70	206.70	206.80	216.00	212.40	114.60	90.20	84.70	43.10	34.10	36.20	51.50
1940	84.20	76.40	83.80	194.70	394.30	707.20	727.90	643.40	527.20	99.80	57.90	91.20
1941	87.80	88.70	166.60	388.00	660.50	1094.00	819.20	990.00	1202.00	510.10	116.30	93.40
1942	118.70	113.10	241.60	464.30	547.30	468.20	572.00	737.20	1113.40	427.50	88.80	101.50
1943	124.10	115.90	210.10	247.20	578.00	1088.20	773.60	683.60	565.20	113.80	79.10	85.70
1944	110.70	101.20	127.70	135.80	144.20	218.60	100.50	140.20	146.20	58.10	49.20	58.40
1945	96.40	117.10	169.20	166.20	496.00	466.90	400.00	600.80	538.90	214.80	95.90	104.40
1946	150.60	177.60	288.60	451.60	278.00	171.60	217.50	557.40	282.70	79.50	62.10	74.20
1947	97.60	131.40	178.80	162.00	118.40	106.60	37.30	52.10	40.30	26.10	27.30	60.60
1948	71.30	89.00	80.40	65.90	34.70	25.40	29.30	123.90	323.80	61.10	36.20	56.20
1949	88.80	73.20	77.20	82.40	61.60	154.50	83.50	83.90	75.30	24.80	30.80	35.90
1950	66.50	82.40	84.20	88.90	145.60	88.70	172.50	99.00	178.70	33.00	30.60	46.00
1951	73.40	341.40	1003.00	455.90	474.60	351.30	93.20	271.90	159.50	41.80	35.40	50.80
1952	82.20	74.80	140.60	445.40	546.00	698.40	942.50	1402.50	1006.30	171.80	76.50	79.20
1953	88.40	94.00	175.30	279.70	158.40	59.90	48.70	66.90	161.10	73.70	35.00	51.20
1954	80.20	73.20	81.90	84.10	104.00	201.60	179.60	270.20	60.70	33.20	31.40	38.20
1955	51.60	59.30	72.70	131.70	102.20	61.00	43.30	42.20	37.30	23.50	23.10	30.40
1956	37.90	47.40	394.60	1303.00	768.60	342.90	244.20	609.00	555.20	148.60	103.30	97.00
1957	94.90	96.00	116.30	100.10	85.00	149.80	70.20	103.30	154.90	43.80	43.40	53.40
1958	101.90	114.20	130.20	103.50	239.40	668.00	1583.00	1121.00	719.60	236.70	87.20	112.90
1959	149.40	209.60	134.20	116.30	137.70	89.80	42.80	43.80	29.00	19.90	22.80	39.20
1960	45.50	52.50	61.40	81.40	90.10	37.00	29.30	32.20	17.90	16.00	17.40	20.80
1961	37.90	52.10	69.70	76.10	55.60	25.30	15.00	24.40	13.50	9.60	12.00	20.00
1962	22.40	30.60	39.20	43.60	271.10	255.40	72.90	87.90	109.00	41.20	36.00	46.70
1963	64.30	70.30	101.80	83.50	374.70	110.40	384.70	410.40	293.40	77.90	48.80	65.30
1964	136.10	155.60	173.80	120.20	70.30	40.90	37.00	38.60	33.80	24.40	27.70	45.00
1965	0.00	0.00	240.60	555.70	324.90	236.90	400.90	227.20	233.90	91.20	63.20	80.40
1966	151.90	173.80	297.00	245.60	169.30	100.10	48.90	42.80	26.90	22.30	24.60	35.40
1967	57.40	67.40	220.60	146.30	267.90	279.40	685.10	970.30	906.60	485.50	101.50	86.80
1968	120.90	162.10	157.10	123.40	122.30	149.30	56.10	45.10	29.10	27.80	42.80	48.10

THIS IS DATA FILE FOR THE TUOLUMNE RIVER FLOW AT TUOLUMNE CITY.

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930 TC	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	69.20	47.00	37.00	58.70
1931 TC	59.30	0.00	0.00	0.00	0.00	0.00	0.00	16.50	15.70	15.50	15.40	15.40
1932 TC	19.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	23.60	23.40
1933 TC	60.80	0.00	0.00	0.00	0.00	0.00	0.00	19.80	90.80	25.70	19.70	39.50
1934 TC	62.50	0.00	0.00	0.00	0.00	0.00	0.00	19.00	17.90	17.70	19.00	17.10
1935 TC	33.30	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	41.60	23.80	40.90
1936 TC	49.70	0.00	0.00	72.90	231.10	247.60	199.20	328.10	258.60	56.30	25.00	30.60
1937 TC	55.90	54.70	79.30	59.80	161.30	210.30	222.30	388.50	222.20	34.00	23.40	36.00
1938 TC	59.50	70.30	0.00	88.10	402.10	444.10	342.70	398.40	620.00	186.10	45.80	56.60
1939 TC	67.30	125.90	88.40	70.90	58.00	38.40	23.90	28.90	20.10	27.50	27.10	29.50
1940 TC	50.50	52.00	50.40	58.60	159.00	293.20	264.20	213.20	184.10	26.70	27.70	52.80
1941 TC	47.90	64.10	83.30	88.30	132.90	270.90	225.90	319.90	390.40	109.00	47.30	45.70
1942 TC	63.50	68.30	107.60	144.80	118.90	141.10	172.80	255.30	445.90	131.80	42.30	52.80
1943 TC	63.40	54.40	132.60	95.30	179.20	378.80	231.70	251.90	214.30	39.40	33.70	44.20
1944 TC	59.10	61.70	78.70	55.20	48.50	74.80	35.20	63.60	40.90	23.20	22.00	21.80
1945 TC	46.50	71.00	118.10	70.20	183.00	167.90	119.90	127.90	238.20	83.00	29.60	35.90
1946 TC	53.50	85.90	121.60	145.50	85.90	58.10	118.80	282.50	119.30	30.10	29.20	24.60
1947 TC	51.10	93.50	86.20	55.30	48.30	49.00	20.60	18.10	16.50	15.20	17.30	39.80
1948 TC	48.40	67.60	53.10	41.90	17.80	18.10	20.90	79.30	174.20	37.40	21.50	24.20
1949 TC	48.30	47.50	52.40	43.70	32.10	80.50	51.10	31.00	23.00	20.60	20.80	19.50
1950 TC	45.60	63.90	63.70	51.80	79.70	51.30	148.70	69.10	113.40	24.00	21.90	21.30
1951 TC	41.80	250.00	522.20	205.70	160.10	181.20	39.70	164.20	108.40	25.10	23.20	21.70
1952 TC	54.30	48.80	98.00	209.90	168.20	277.50	390.70	481.50	302.30	50.00	26.10	26.50
1953 TC	41.70	67.30	132.20	128.20	93.90	30.30	29.70	36.00	120.20	68.50	22.80	20.10
1954 TC	49.10	48.10	52.70	54.10	47.30	134.00	85.00	125.90	24.60	20.50	19.80	18.50
1955 TC	31.40	38.90	46.40	72.10	69.60	37.90	20.40	19.00	17.20	16.30	16.20	22.00
1956 TC	22.00	34.80	294.80	507.00	236.10	145.20	108.80	204.30	190.80	69.50	59.40	52.30
1957 TC	51.30	64.10	80.40	58.60	37.60	70.30	29.30	33.40	51.10	21.90	20.70	21.40
1958 TC	60.60	88.90	96.80	55.60	95.10	288.10	530.50	444.30	305.00	106.00	29.60	46.90
1959 TC	93.90	162.00	96.10	66.70	92.60	46.10	21.40	20.50	17.40	16.40	15.60	16.80
1960 TC	26.20	34.20	42.20	48.50	39.60	21.70	16.40	15.40	13.40	13.40	13.20	14.10
1961 TC	27.40	35.80	52.10	43.20	23.90	14.80	11.00	10.90	9.90	8.80	10.50	13.60
1962 TC	14.60	20.30	16.60	12.60	102.20	120.20	37.90	22.30	18.60	17.90	19.20	23.00
1963 TC	42.50	60.10	105.50	54.10	0.00	0.00	155.20	125.20	122.10	44.60	25.10	23.40
1964 TC	69.30	131.10	147.30	73.10	37.80	19.30	16.50	15.50	14.30	12.50	12.60	14.40
1965 TC	21.90	82.80	189.40	378.40	209.80	97.70	240.10	89.00	107.50	45.80	25.90	0.00
1966 TC	115.60	120.00	159.40	113.00	96.60	56.70	21.10	18.30	14.40	13.50	13.10	13.10
1967 TC	34.40	40.10	164.70	80.90	144.80	201.50	341.10	239.40	326.80	218.50	25.00	23.10
1968 TC	49.70	116.60	94.70	63.70	59.80	92.10	20.80	14.90	12.00	12.40	15.30	15.20
1969 TC	23.50	30.00	98.10	359.20	437.60	289.70	285.10	376.80	458.20	88.60	16.50	35.20

END OF FILE

THIS IS THE DATA FILE FOR SAN JOAQUIN RIVER FLOW AT NEWMAN.

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930 NM	8.90	8.50	9.70	26.30	19.70	29.80	19.00	20.10	18.90	12.70	12.40	12.30
1931 NM	11.10	10.90	14.60	28.80	28.70	17.10	7.30	7.10	6.80	3.60	2.60	3.10
1932 NM	4.50	5.10	24.80	151.00	309.00	141.00	96.40	223.00	339.00	164.00	21.20	19.60
1933 NM	19.70	13.80	24.60	62.10	98.90	38.90	24.30	27.40	94.60	21.60	12.90	14.50
1934 NM	11.70	9.90	21.00	86.10	62.20	40.90	15.80	12.10	10.90	8.20	5.60	5.60
1935 NM	7.10	8.40	18.50	110.40	118.80	152.60	368.30	430.00	375.30	78.80	22.80	20.50
1936 NM	31.80	38.00	58.40	79.20	388.90	349.50	368.80	451.40	222.90	77.40	26.90	26.30
1937 NM	28.20	36.40	77.60	104.60	499.10	439.10	413.00	528.50	479.10	109.60	26.30	26.30
1938 NM	28.60	21.00	174.10	233.80	797.00	1445.00	683.00	941.20	1250.00	530.30	107.30	45.70
1939 NM	43.50	63.30	89.30	120.90	135.60	41.80	57.10	38.60	19.80	14.40	13.80	16.50
1940 NM	13.90	11.30	26.00	135.10	260.80	411.70	394.80	426.40	324.30	55.50	22.80	23.00
1941 NM	20.10	12.80	79.50	278.60	538.90	769.90	548.20	689.50	755.90	345.50	44.40	29.60
1942 NM	25.20	25.00	126.00	314.30	389.60	285.70	370.90	427.80	657.10	249.70	37.30	30.40
1943 NM	33.60	43.00	79.80	163.70	405.10	762.90	555.00	437.30	325.20	52.80	27.50	26.80
1944 NM	29.50	19.70	37.80	74.10	87.20	129.00	51.90	61.10	88.40	31.40	25.60	25.80
1945 NM	31.10	35.00	45.10	82.80	311.80	274.30	257.70	414.80	301.50	107.70	51.80	47.20
1946 NM	67.00	74.30	155.60	278.10	178.10	83.30	93.90	259.80	128.90	40.80	29.00	34.30
1947 NM	26.90	30.30	81.80	92.00	60.70	54.00	25.60	40.00	28.80	20.10	17.40	19.80
1948 NM	14.10	14.70	16.10	18.00	11.80	13.10	21.90	35.70	136.60	20.00	20.10	28.40
1949 NM	20.70	13.20	13.20	21.90	19.80	59.80	29.20	38.90	49.80	14.60	15.60	15.70
1950 NM	10.60	11.00	12.50	29.40	60.60	34.00	33.90	34.10	60.90	13.70	14.20	18.40
1951 NM	12.60	61.10	408.70	253.40	295.30	142.30	47.40	110.00	42.80	20.60	18.60	23.00
1952 NM	16.90	14.80	30.60	250.60	316.80	386.80	525.60	687.00	625.30	71.20	34.50	36.40
1953 NM	28.10	17.00	58.70	149.90	45.70	21.00	22.80	31.40	28.10	14.30	14.80	22.30
1954 NM	15.60	12.40	14.70	23.60	54.50	54.90	58.40	121.20	32.60	17.80	17.30	17.50
1955 NM	10.80	12.40	16.10	50.10	29.30	21.40	22.40	26.50	20.50	15.20	14.50	14.40
1956 NM	10.10	9.70	198.20	711.40	508.40	186.10	78.90	284.50	261.10	46.70	26.70	30.60
1957 NM	26.70	15.60	15.10	26.40	37.10	75.70	45.40	48.50	104.20	21.00	21.70	22.50
1958 NM	19.40	12.60	17.70	43.90	111.70	318.70	827.30	659.40	426.10	84.60	31.50	37.00
1959 NM	25.90	13.10	16.90	35.00	42.90	28.90	24.90	26.80	16.20	11.00	11.40	12.90
1960 NM	9.80	9.90	12.80	24.30	42.50	18.50	16.40	19.70	12.00	9.80	10.40	7.80
1961 NM	6.40	9.50	13.40	24.60	21.80	13.80	11.20	14.50	10.40	6.00	6.30	6.60
1962 NM	5.60	8.30	17.60	28.30	193.90	141.10	33.20	64.90	94.40	22.30	19.30	18.90
1963 NM	15.40	15.90	19.10	25.80	156.40	53.50	133.40	200.40	126.20	27.50	22.60	25.10
1964 NM	37.20	23.40	23.30	31.20	18.70	15.70	18.30	21.60	19.90	13.00	13.40	20.50
1965 NM	38.50	41.10	61.40	247.70	91.10	129.20	155.70	118.50	113.30	32.00	27.40	31.00
1966 NM	19.50	52.80	130.10	97.70	37.00	24.40	23.10	21.60	16.60	12.60	11.10	11.30
1967 NM	10.30	17.00	52.00	38.80	96.40	62.90	376.50	716.00	539.10	277.50	63.70	44.50
1968 NM	48.90	33.80	58.80	55.10	52.20	38.20	27.10	25.90	14.70	13.80	22.30	23.70
1969 NM	29.30	35.20	38.90	332.40	979.40	1129.00	750.00	758.30	830.70	149.40	63.10	89.00

END OF FILE

THIS IS THE DATA FILE FOR SAN JOAQUIN RIVER FLOW AT NEWMAN.

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930 NM	8.90	8.50	9.70	26.30	19.70	29.80	19.00	20.10	18.90	12.70	12.40	12.30
1931 NM	11.10	10.90	14.60	28.80	28.70	17.10	7.30	7.10	6.80	3.60	2.60	3.10
1932 NM	4.50	5.10	24.80	151.00	309.00	141.00	96.40	223.00	339.00	164.00	21.20	19.60
1933 NM	19.70	13.80	24.60	62.10	98.90	38.90	24.30	27.40	94.60	21.60	12.90	14.50
1934 NM	11.70	9.90	21.00	86.10	62.20	40.90	15.80	12.10	10.90	8.20	5.60	5.60
1935 NM	7.10	8.40	18.50	110.40	118.80	152.60	368.30	430.00	375.30	78.80	22.80	20.50
1936 NM	31.80	38.00	58.40	79.20	389.90	349.50	368.80	451.40	222.90	77.40	26.90	26.30
1937 NM	28.20	36.40	77.60	104.60	490.10	439.10	413.00	528.50	479.10	109.60	26.30	26.30
1938 NM	28.60	21.00	174.10	233.80	797.00	1445.00	683.00	941.20	1250.00	530.30	107.30	45.70
1939 NM	43.50	63.30	89.30	120.90	135.60	41.80	57.10	38.60	19.80	14.40	13.80	16.50
1940 NM	13.90	11.30	26.00	135.10	260.80	411.70	394.80	426.40	324.30	55.50	22.80	23.00
1941 NM	20.10	12.80	79.50	278.60	538.90	769.90	548.20	689.50	755.90	345.50	44.40	29.60
1942 NM	25.20	25.00	126.00	314.30	389.60	285.70	370.90	427.80	657.10	249.70	37.30	30.40
1943 NM	33.60	43.00	79.80	163.70	405.10	762.90	555.00	437.30	325.20	52.80	27.50	26.80
1944 NM	29.50	19.70	37.80	74.10	87.20	129.00	51.90	61.10	88.40	31.40	25.60	25.80
1945 NM	31.10	35.00	45.10	82.80	311.80	274.30	257.70	414.80	301.50	107.70	51.80	47.20
1946 NM	67.00	74.30	155.60	278.10	178.10	83.30	93.90	259.80	128.90	40.80	29.00	34.30
1947 NM	26.90	30.30	81.80	92.00	60.70	54.00	25.60	40.00	28.80	20.10	17.40	19.80
1948 NM	14.10	14.70	16.10	18.00	11.80	13.10	21.90	35.70	136.60	20.00	20.10	28.40
1949 NM	20.70	13.20	13.20	21.90	19.80	59.80	29.20	38.90	49.80	14.60	15.60	15.70
1950 NM	10.60	11.00	12.50	29.40	60.60	34.00	33.90	34.10	60.90	13.70	14.20	18.40
1951 NM	12.60	61.10	408.70	253.40	295.30	142.30	47.40	110.00	42.80	20.60	18.60	23.00
1952 NM	16.90	14.80	30.60	250.60	316.80	386.80	525.60	687.00	625.30	71.20	34.50	36.40
1953 NM	28.10	17.00	58.70	149.90	45.70	21.00	22.80	31.40	23.10	14.30	14.80	22.30
1954 NM	15.60	12.40	14.70	23.60	54.50	54.90	58.40	121.20	32.60	17.80	17.30	17.50
1955 NM	10.80	12.40	16.10	50.10	29.30	21.40	22.40	26.50	20.50	15.20	14.50	14.40
1956 NM	10.10	9.70	198.20	711.40	508.40	186.10	78.90	284.50	261.10	46.70	26.70	30.60
1957 NM	26.70	15.60	15.10	26.40	37.10	75.70	45.40	48.50	104.20	21.00	21.70	22.50
1958 NM	19.40	12.60	17.70	43.90	111.70	318.70	827.30	659.40	426.10	84.60	31.50	37.00
1959 NM	25.90	13.10	16.90	35.00	42.90	28.90	24.90	26.80	16.20	11.00	11.40	12.90
1960 NM	9.80	9.90	12.80	24.30	42.50	18.50	16.40	19.70	12.00	9.80	10.40	7.80
1961 NM	6.40	9.50	13.40	24.60	21.80	13.80	11.20	14.50	10.40	6.00	6.30	6.60
1962 NM	5.60	8.30	17.60	28.30	193.90	141.10	33.20	64.90	94.40	22.30	19.30	18.90
1963 NM	15.40	15.90	19.10	25.80	156.40	53.50	133.40	200.40	126.20	27.50	22.60	25.10
1964 NM	37.20	23.40	23.30	31.20	18.70	15.70	18.30	21.60	19.90	13.00	13.40	20.50
1965 NM	38.50	41.10	61.40	247.70	91.10	129.20	155.70	118.50	113.30	32.00	27.40	31.00
1966 NM	19.50	52.80	130.10	97.70	37.00	24.40	23.10	21.60	16.60	12.60	11.10	11.30
1967 NM	10.30	17.00	52.00	38.80	96.40	62.90	376.50	716.00	539.10	277.50	63.70	44.50
1968 NM	48.90	33.80	58.80	55.10	52.20	38.20	27.10	25.90	14.70	13.80	22.30	23.70
1969 NM	29.30	35.20	38.90	332.40	979.40	1129.00	750.00	758.30	830.70	149.40	63.10	89.00

END OF FILE

```
JOB ACTIVE.
list,f=vufile
 THIS IS THE DATA FILE OF UNIMPAIRED FLOW AT VERNALIS.
```

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930 VU	9.70	12.20	57.20	102.10	182.50	400.50	713.70	796.30	773.60	152.50	34.04	20.46
1931 VU	27.36	51.51	33.67	70.02	107.90	167.30	422.95	563.45	151.50	36.70	17.60	10.19
1932 VU	12.00	24.20	316.80	236.00	680.60	524.40	817.60	1673.20	1628.70	561.60	112.10	35.40
1933 VU	29.60	22.80	38.30	81.40	91.40	237.10	535.20	794.20	1200.30	245.70	54.50	25.70
1934 VU	12.10	28.90	125.70	163.90	230.60	425.00	544.90	420.40	239.70	56.20	24.20	16.80
1935 VU	33.30	108.50	130.40	300.40	290.10	404.30	1414.60	1728.90	1538.80	348.80	91.30	28.90
1936 VU	34.90	52.20	50.40	234.90	1009.00	625.40	1250.40	1662.00	1096.00	376.40	82.00	21.90
1937 VU	26.30	33.20	94.00	112.00	863.50	655.90	956.30	2149.40	1212.80	335.00	70.10	21.60
1938 VU	27.30	47.00	844.40	291.00	945.80	1425.20	1389.00	2498.80	2459.60	990.10	243.20	86.60
1939 VU	119.87	117.63	97.90	118.67	152.39	393.74	850.90	638.68	253.55	83.48	36.58	45.47
1940 VU	111.58	47.24	50.10	614.27	698.75	967.46	1055.72	1780.52	1005.96	206.31	45.40	13.40
1941 VU	32.20	39.90	361.60	348.00	659.20	785.50	866.60	2202.30	1705.30	745.50	156.20	42.70
1942 VU	47.20	97.50	409.60	478.10	431.20	473.70	1075.90	1577.10	1890.70	749.60	133.50	34.70
1943 VU	31.56	209.75	236.59	715.74	490.72	1181.94	1254.17	1591.95	997.98	434.53	106.38	32.44
1944 VU	34.92	47.17	62.51	113.60	215.08	406.96	487.09	1372.99	803.72	313.03	61.72	20.05
1945 VU	30.02	232.17	214.58	162.62	911.63	524.49	926.16	1529.06	1387.33	533.99	120.24	39.28
1946 VU	162.65	257.53	555.41	339.16	206.58	479.22	1091.18	1521.44	793.04	239.60	60.20	28.08
1947 VU	67.02	197.81	241.00	138.66	229.90	392.55	604.57	1055.02	370.13	89.69	22.12	16.44
1948 VU	88.06	67.42	50.83	96.56	74.83	188.55	649.70	1380.41	1271.07	285.30	46.27	19.42
1949 VU	25.05	33.85	57.56	61.96	107.02	336.65	890.61	1359.82	736.33	130.67	38.89	20.83
1950 VU	20.80	43.23	45.12	200.66	348.87	366.58	1037.36	1419.17	901.25	215.82	38.69	19.14
1951 VU	58.29	1395.26	1494.97	478.82	429.31	501.43	763.11	1080.94	753.76	235.20	54.14	16.88
1952 VU	35.92	78.22	322.04	617.42	418.42	716.58	1393.43	2647.17	1910.71	885.42	218.67	67.97
1953 VU	37.20	49.17	151.67	367.88	180.56	292.57	798.35	785.41	1124.88	479.18	65.00	22.44
1954 VU	27.02	50.33	60.65	116.59	258.36	585.84	1063.52	1371.46	569.67	163.93	31.12	16.19
1955 VU	18.50	49.04	124.84	176.51	169.95	249.94	439.02	1128.28	925.17	177.11	36.61	16.96
1956 VU	17.30	40.00	1831.30	1207.30	494.10	555.00	923.60	1846.70	1761.00	759.90	176.70	66.90
1957 VU	67.70	75.60	69.00	94.70	294.00	422.30	540.30	1188.10	1209.10	250.70	55.20	25.80
1958 VU	45.14	61.08	133.25	169.38	491.84	774.83	1319.13	2535.83	1822.49	722.78	217.41	73.65
1959 VU	38.65	37.69	33.39	174.57	330.68	375.87	694.22	667.98	410.46	82.76	21.29	118.07
1960 VU	37.82	26.55	30.64	68.38	291.52	398.28	703.09	847.07	443.46	77.27	23.20	13.63
1961 VU	16.37	57.31	92.03	56.44	119.50	195.99	481.55	606.47	353.92	57.17	43.76	19.51
1962 VU	18.65	32.64	66.90	68.87	673.90	399.52	1240.79	1217.04	1362.56	427.62	81.69	28.67
1963 VU	56.49	31.68	66.20	285.40	907.54	343.03	728.87	1683.95	1386.11	575.68	128.36	56.85
1964 VU	59.85	256.78	134.83	143.59	133.16	206.91	495.68	903.16	612.32	135.85	45.18	23.77
1965 VU	69.12	153.05	1143.86	877.22	437.81	455.60	964.37	1381.29	1423.25	710.37	353.72	138.32
1966 VU	38.66	350.81	238.94	223.72	202.78	438.75	940.10	1066.90	322.48	96.33	41.29	24.95
1967 VU	29.44	132.56	663.70	377.93	349.53	912.80	930.90	2165.70	2487.10	1517.20	309.30	116.57
1968 VU	50.70	53.60	94.00	125.90	352.60	343.90	572.30	801.80	392.20	86.40	43.40	21.70
1969 VU	37.40	182.00	218.70	1477.70	818.70	808.10	1564.00	3317.00	3734.00	1876.50	341.60	68.80

THIS IS THE DATA FILE FOR UNIMPAIRED SAN JOAQUIN RIVER FLOW (KAF) AT FRIANT.

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930 FR	5.00	6.20	8.30	18.20	35.60	80.00	165.10	213.50	243.60	60.80	16.90	5.90
1931 FR	10.60	13.40	10.20	16.00	23.40	38.90	100.20	173.50	59.70	16.00	11.10	7.20
1932 FR	5.90	8.40	71.80	58.90	167.70	156.60	238.10	491.50	543.60	238.80	51.40	14.70
1933 FR	12.60	8.90	14.60	26.50	30.00	73.40	159.00	213.40	410.10	118.90	29.30	14.70
1934 FR	6.80	10.30	38.10	46.80	50.30	109.40	166.10	146.20	68.90	27.30	13.40	7.90
1935 FR	12.60	26.60	36.20	72.50	85.20	110.90	356.60	496.80	519.20	144.20	43.80	18.60
1936 FR	13.60	15.80	16.40	38.30	195.90	163.50	348.60	510.00	347.70	150.50	42.10	10.90
1937 FR	10.90	12.60	36.40	84.90	252.70	190.60	303.80	704.80	456.80	159.70	34.00	10.80
1938 FR	9.80	12.30	210.70	70.90	207.30	433.80	434.20	795.00	912.70	431.20	127.90	42.60
1939 FR	38.90	33.10	28.70	32.70	43.30	102.80	239.90	208.80	110.30	43.40	24.80	14.10
1940 FR	34.80	14.20	11.40	134.10	139.80	210.00	290.00	558.60	362.90	96.60	21.20	7.00
1941 FR	10.10	11.70	98.40	105.80	182.80	208.60	242.40	711.20	641.50	330.90	85.80	23.30
1942 FR	21.50	30.30	96.00	113.10	102.60	128.50	298.50	465.40	632.60	284.00	64.70	16.70
1943 FR	10.10	42.50	43.40	169.70	113.30	267.70	335.10	502.50	325.10	178.80	49.90	15.60
1944 FR	10.50	15.10	19.80	31.20	55.40	111.60	140.80	408.20	279.50	142.60	35.00	15.70
1945 FR	12.70	58.40	56.10	44.10	237.70	147.90	275.90	476.80	487.60	240.20	73.90	26.80
1946 FR	59.10	65.60	118.30	78.90	53.80	125.80	310.40	463.90	279.90	117.80	36.90	19.10
1947 FR	28.50	64.90	84.50	47.70	64.00	100.30	171.00	347.70	145.80	42.70	16.80	11.60
1948 FR	22.80	18.20	15.40	18.90	20.20	42.60	164.60	390.60	372.60	107.90	26.00	15.00
1949 FR	10.50	7.90	14.60	16.20	25.90	73.00	234.50	409.50	268.30	63.20	25.60	14.90
1950 FR	9.80	16.10	17.20	43.20	90.10	89.60	280.10	379.00	262.90	87.00	21.70	13.80
1951 FR	17.10	247.00	300.40	111.20	104.20	119.20	201.90	321.90	278.00	114.70	31.70	11.70
1952 FR	12.30	20.40	83.40	133.00	98.70	176.70	385.20	819.90	640.80	335.30	101.40	33.00
1953 FR	16.90	18.70	42.90	85.00	48.00	71.50	197.20	211.30	320.20	171.60	30.20	13.20
1954 FR	9.40	16.60	16.60	33.40	65.40	127.20	278.40	439.50	217.60	80.40	20.20	9.10
1955 FR	6.00	17.80	31.20	41.60	48.90	74.10	126.50	337.80	348.20	87.90	29.60	11.40
1956 FR	6.10	13.20	460.50	271.20	140.80	169.50	278.30	568.00	613.80	317.80	86.50	34.40
1957 FR	26.30	21.70	20.70	29.50	66.90	90.10	142.20	326.70	439.90	115.00	31.70	15.90
1958 FR	16.40	18.50	43.30	42.60	112.50	181.40	362.60	795.50	622.30	287.50	107.90	40.50
1959 FR	16.10	14.60	14.60	37.00	89.60	113.60	203.10	208.10	153.00	41.50	16.80	41.40
1960 FR	18.40	9.70	9.50	18.00	55.00	86.10	177.90	240.70	146.90	42.60	16.40	7.50
1961 FR	8.50	22.30	31.20	19.00	30.80	48.90	124.60	171.60	128.00	27.40	24.80	10.40
1962 FR	9.80	14.90	23.10	23.50	184.80	109.90	381.00	396.90	505.20	202.60	51.70	20.20
1963 FR	17.60	10.80	10.70	81.90	207.90	101.40	191.90	464.20	492.40	264.20	70.70	31.40
1964 FR	25.50	64.30	36.40	31.20	30.80	51.80	126.70	256.90	200.00	59.30	28.70	10.50
1965 FR	10.10	34.00	203.90	187.80	114.10	128.20	250.80	431.20	472.20	266.70	137.80	35.10
1966 FR	17.50	101.10	66.50	61.90	55.50	125.80	276.90	361.60	147.70	50.40	25.00	8.80
1967 FR	6.40	29.70	212.70	92.50	100.70	243.00	249.60	659.90	823.50	594.30	154.20	66.80
1968 FR	26.90	22.90	34.30	36.90	75.40	82.90	146.10	231.10	131.20	43.80	22.10	8.40
1969 FR	15.10	40.00	52.20	396.60	233.60	227.20	464.50	1096.40	874.20	462.80	137.10	40.50
1970 FR	32.60	31.70	47.10	150.40	83.30	136.90	146.00	375.80	278.50	106.60	36.70	11.00

list,1 ernali
THIS IS THE DATA FILE CHLORIDES (PPM) AT VERNALIS

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	0	0	0	0	0	0	0	0	0	0	0	0
1931	0	0	0	0	0	0	0	0	0	0	0	0
1932	0	0	0	0	0	0	0	0	0	0	0	0
1933	0	0	0	0	0	0	0	0	0	0	0	0
1934	0	0	0	0	0	0	0	0	0	0	0	0
1935	0	0	0	0	0	0	0	0	0	0	0	0
1936	0	0	0	0	0	0	0	0	0	0	0	0
1937	0	0	0	0	0	0	0	0	0	0	0	0
1938	0	0	0	20	0	18	18	10	7	8	53	82
1939	47	32	41	30	31	84	0	0	0	0	0	0
1940	0	0	0	0	0	0	0	0	0	0	0	0
1941	0	0	0	0	0	0	0	0	0	0	0	0
1942	0	0	0	17	21	23	9	8	8	52	78	72
1943	59	43	26	27	11	13	10	7	24	88	80	64
1944	66	66	48	49	35	49	42	23	86	120	98	78
1945	61	52	37	43	19	17	14	18	7	0	0	0
1946	0	0	0	26	31	66	16	10	62	120	100	110
1947	83	59	62	71	77	78	80	63	140	160	150	76
1948	85	84	94	77	180	160	29	10	14	140	120	100
1949	88	0	96	68	130	30	70	60	110	140	130	140
1950	93	100	100	62	37	63	18	16	76	140	140	110
1951	78	10	0	0	0	0	0	0	0	0	0	0
1952	80	86	52	21	15	18	10	9	10	58	106	83
1953	89	78	48	32	72	147	108	66	23	54	134	123
1954	94	97	94	107	80	45	28	23	132	177	167	160
1955	140	113	94	33	79	106	121	142	71	174	170	159
1956	163	143	63	13	25	57	40	14	14	68	92	89
1957	93	84	64	100	124	61	133	100	39	152	151	135
1958	84	72	70	93	52	34	21	16	16	62	125	100
1959	0	0	50	97	83	109	172	178	201	256	240	172
1960	161	138	124	138	125	236	199	193	263	281	272	263
1961	175	140	110	129	168	252	348	253	315	407	401	286
1962	250	194	196	213	110	49	96	55	67	162	186	154
1963	124	101	67	129	44	97	27	15	36	109	167	130
1964	87	70	50	58	95	209	223	171	146	248	259	182
1965	112	108	92	21	35	46	42	32	21	88	153	122
1966	28	32	11	36	37	112	66	52	90	0	110	112
1967	89	37	31	53	25	35	12	12	9	26	34	101
1968	75	56	50	32	108	35	32	82	0	214	188	179
1969	75	42	94	2	6	15	13	8	4	17	49	35

READY.

list,f=graflow

THIS IS THE DATA FILE OF CHLORIDES (PPM) AT GRAYSON

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	0	0	0	0	0	0	0	0	0	0	0	0
1931	0	0	0	0	0	0	0	0	0	0	0	0
1932	0	0	0	0	0	0	0	0	0	0	0	0
1933	0	0	0	0	0	0	0	0	0	0	0	0
1934	0	0	0	0	0	0	195	199	213	240	202	0
1935	0	0	0	0	0	0	0	0	0	0	159	0
1936	0	0	0	^	0	0	0	0	0	0	189	0
1937	0	0	0		0	0	0	0	0	0	0	100
1938	112	0	0		0	22	0	12	8	9	54	99
1939	89	54	57		50	180	50	31	88	135	124	111
1940	97	184	110	/	22	24	13	3	9	80	131	87
1941	113	187	117	26	20	23	20	9	6	40	153	100
1942	98	137	52	19	28	19	16	11	7	38	130	112
1943	93	130	66	69	19	14	10	16	16	118	91	94
1944	0	0	8	52	34	49	66	56	73	130	84	69
1945	78	100	1	62	17	18	29	13	9	0	0	0
1946	0	0	0		0	0	0	0	0	0	0	0
1947	66	168	0	56	0	206	0	148	127	185	0	0
1948	0	207	0	175	0	0	246	0	0	0	0	0
1949	0	0	0	0	0	0	0	0	0	0	0	0
1950	0	0	0	0	0	0	0	0	0	0	0	0
1951	0	0	0	0	0	0	123	35	148	146	184	95
1952	169	205	97	16	22	35	13	6	8	116	127	76
1953	153	168	130	36	161	232	180	103	134	190	159	91
1954	106	192	212	250	119	174	41	21	96	168	155	170
1955	210	224	209	116	174	218	177	114	176	191	159	184
1956	234	222	191	17	25	78	120	28	12	132	154	122
1957	118	192	198	191	170	102	179	131	36	159	146	128
1958	162	218	192	66	65	100	0	18	12	111	165	100
1959	112	216	240	160	250	277	218	220	228	235	0	0
1960	181	225	280	250	205	306	248	213	248	210	191	238
1961	270	239	225	235	0	318	288	180	175	200	256	257
1962	295	298	205	233	292	53	220	232	39	158	161	158
1963	208	0	282	309	42	210	0	70	37	114	168	148
1964	115	231	225	186	238	343	240	155	162	216	0	154
1965	115	204	208	57	127	21	118	0	65	126	156	116
1966	122	245	30	96	228	305	0	0	0	0	0	0
1967	0	0	0	0	0	0	0	0	0	0	0	0
1968	0	0	0	0	0	0	0	0	0	0	0	0
1969	0	0	0	0	0	0	0	0	0	0	0	0

THIS IS THE DATA FILE OF CHLORIDES (PPM) AT MAZE ROAD BRIDGE.

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	0	0	0	0	0	0	0	0	0	0	0	0
1931	0	0	0	0	0	0	0	0	0	0	0	0
1932	0	0	0	0	0	0	0	0	0	0	0	0
1933	0	0	0	0	0	0	0		0	0	0	0
1934	0	0	0	0	0	0	0	J	0	0	0	0
1935	0	0	0	0	0	0	C	0	0	0	0	0
1936	0	0	0	0	0	0	0	0	0	0	0	0
1937	0	0	0	0	0	C	0	0	0	0	0	0
1938	0	0	0	0	0			0	0	0	0	0
1939	0	0	0	0	0	/	90	56	146	108	106	94
1940	78	82	72	35	15	24	11	10	9	54	126	66
1941	73	85	74	24	0	15	21	13	7	46	79	79
1942	67	75	49	0	17	0	0	0	0	50	0	90
1943	62	0	39	0		0	0	0	0	120	0	99
1944	0	0	0	0		0	68	0	0	0	107	0
1945	0	0	0	0		0	0	0	0	0	0	0
1946	0	0	0	0	0	0	0	0	0	0	0	0
1947	91	74	0		0	211	0	187	170	162	0	0
1948	0	87	0		0	0	213	0	0	0	0	0
1949	0	0	0	0	0	0	0	0	0	0	0	0
1950	0	0	0	0	0	0	0	0	0	0	0	0
1951	0	0	0	0	0	0	75	13	37	92	60	46
1952	0	58	?	8	11	9	0	0	0	116	136	65
1953	0	70	/	34	73	0	0	72	69	33	166	0
1954	0	117	20	0	0	230	31	31	95	196	194	194
1955	198	1?	137	0	0	0	213	216	199	198	191	187
1956	206		124	18	23	0	0	19	20	154	127	91
1957	103		84	142	150	45	205	154	42	172	165	140
1958	82	74	88	67	24	60	23	17	16	80	164	81
1959	110	55	109	119	120	146	195	210	240	295	0	262
1960	227	132	104	135	175	190	280	250	285	278	246	269
1961	260	144	132	122	0	287	325	206	258	344	0	0
1962	0	0	0	0	0	0	0	0	0	0	0	0
1963	0	0	0	0	0	0	0	0	0	0	0	0
1964	89	80	60	89	151	271	218	0	0	265	0	180
1965	139	132	98	49	42	25	52	0	76	117	0	25
1966	66	82	22	74	67	126	220	222	190	244	0	245
1967	0	0	0	0	0	0	0	0	0	0	0	0
1968	0	0	0	0	0	0	0	0	0	0	0	0
1969	0	0	0	0	0	0	0	0	0	0	0	0

END OF FILE

list,f=tuoflow

THIS IS THE DATA FILE OF CHLORIDES (PPM) FROM THE TUOLUMNE

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	0	0	0	0	0	0	0	0	0	0	0	0
1931	0	0	0	0	0	0	0	0	0	0	0	0
1932	0	0	0	0	0	0	0	0	0	0	0	0
1933	0	0	0	0	0	0	0	0	0	0	0	0
1934	0	0	0	0	0	0	0	0	0	0	0	0
1935	0	0	0	0	0	0	0	0	0	0	0	0
1936	0	0	0	0	0	0	0	0	0	0	0	0
1937	0	0	0	0	0	0	0	0	0	0	0	0
1938	0	30	0	18	0	7	13	8	3	11	35	41
1939	31	16	28	37	37	41	46	23	12	9	13	12
1940	7	9	14	11	4	5	5	2	5	27	36	13
1941	25	20	22	20	5	7	7	6	2	17	40	17
1942	25	13	12	10	16	9	9	7	9	27	49	30
1943	25	52	11	33	10	12	17	41	24	22	42	27
1944	49	37	34	52	60	83	20	31	110	60	60	110
1945	51	32	26	38	35	14	21	77	6	0	0	0
1946	0	0	0	0	0	0	0	0	0	0	0	0
1947	0	0	0	0	0	0	0	0	0	0	0	0
1948	0	0	0	0	0	0	0	0	0	0	0	0
1949	0	0	0	0	0	0	0	0	0	0	0	0
1950	0	0	0	0	0	0	0	0	0	0	0	0
1951	0	0	0	0	0	0	0	9	15	62	48	79
1952	29	30	17	0	7	0	0	0	0	13	38	27
1953	0	10	13	10	20	0	0	88	54	24	114	122
1954	0	0	74	34	34	90	13	7	61	130	62	0
1955	69	45	37	63	62	72	195	186	151	150	146	151
1956	155	121	74	7	20	28	38	11	79	56	95	73
1957	74	63	46	70	108	20	166	170	74	178	183	153
1958	54	38	44	63	10	25	9	13	18	42	176	68
1959	85	23	66	75	54	67	171	169	210	206	0	222
1960	238	86	62	73	107	112	223	236	235	238	210	218
1961	232	94	70	65	0	218	0	207	255	298	283	179
1962	189	196	162	170	190	9	45	136	135	138	184	164
1963	0	0	39	61	11	66	24	24	34	0	168	181
1964	69	31	21	38	70	185	192	172	0	222	0	202
1965	152	66	48	21	12	27	21	0	76	76	134	30
1966	38	36	20	35	17	38	143	198	185	216	0	209
1967	0	0	0	0	0	0	0	0	0	0	0	0
1968	0	0	0	0	0	0	0	0	0	0	0	0
1969	174	0	0	0	0	0	0	0	0	0	0	0

list,f=graflow

THIS IS THE DATA FILE OF CHLORIDES (PPM) AT GRAYSON

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	0	0	0	0	0	0	0	0	0	0	0	0
1931	0	0	0	0	0	0	0	0	0	0	0	0
1932	0	0	0	0	0	0	0	0	0	0	0	0
1933	0	0	0	0	0	0	0	0	0	0	0	0
1934	0	0	0	0	0	0	195	199	213	240	202	0
1935	0	0	0	0	0	0	0	0	0	0	159	0
1936	0	0	0	0	0	0	0	0	0	0	189	0
1937	0	0	0	0	0	0	0	0	0	0	0	100
1938	112	0	0	23	0	22	0	12	8	9	54	99
1939	89	54	57	73	50	180	50	31	88	135	124	111
1940	97	184	110	39	22	24	13	3	9	80	131	87
1941	113	187	117	26	20	23	20	9	6	40	153	100
1942	98	137	52	19	28	19	16	11	7	38	130	112
1943	93	130	66	69	19	14	10	16	16	118	91	94
1944	0	0	88	52	34	49	66	56	73	130	84	69
1945	78	100	110	62	17	18	29	13	9	0	0	0
1946	0	0	0	0	0	0	0	0	0	0	0	0
1947	66	168	0	56	0	206	0	148	127	185	0	0
1948	0	207	0	175	0	0	246	0	0	0	0	0
1949	0	0	0	0	0	0	0	0	0	0	0	0
1950	0	0	0	0	0	0	0	0	0	0	0	0
1951	0	0	0	0	0	0	123	35	148	146	184	95
1952	169	205	97	16	22	35	13	6	8	116	127	76
1953	153	168	130	36	161	232	180	103	134	190	159	91
1954	106	192	212	250	119	174	41	21	96	168	155	170
1955	210	224	209	116	174	218	177	114	176	191	159	184
1956	234	222	191	17	25	78	120	28	12	132	154	122
1957	118	192	198	191	170	102	179	131	36	159	146	128
1958	162	218	192	66	65	100	0	18	12	111	165	100
1959	112	216	240	160	250	277	218	220	228	235	0	0
1960	181	225	280	250	205	306	248	213	248	210	191	238
1961	270	239	225	235	0	318	288	180	175	200	256	257
1962	295	298	205	233	292	53	220	232	39	158	161	158
1963	208	0	282	309	42	210	0	70	37	114	168	148
1964	115	231	225	186	238	343	240	155	162	216	0	154
1965	115	204	208	57	127	21	118	0	65	126	156	116
1966	122	245	30	96	228	305	0	0	0	0	0	0
1967	0	0	0	0	0	0	0	0	0	0	0	0
1968	0	0	0	0	0	0	0	0	0	0	0	0
1969	0	0	0	0	0	0	0	0	0	0	0	0

READY

list,f-newman

THIS IS THE DATA FILE OF CHLORIDES (PPM) AT NEWMAN

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1930	0	0	0	0	0	0	0	0	0	0	0	0
1931	0	0	0	0	0	0	0	0	0	0	0	0
1932	0	0	0	0	0	0	0	0	0	0	0	0
1933	0	0	0	0	0	0	0	0	0	0	0	0
1934	0	0	0	0	0	0	0	0	0	0	0	0
1935	0	0	0	0	0	0	0	0	0	0	0	0
1936	0	0	0	0	0	0	0	0	0	119	171	92
1937	73	0	45	0	0	0	0	0	0	73	168	95
1938	77	0	0	23	33	14	0	9	8	4	86	70
1939	59	43	44	50	44	110	56	76	130	160	120	78
1940	160	170	51	39	24	40	22	6	8	52	150	88
1941	120	140	0	34	29	28	20	10	6	39	140	77
1942	82	66	31	26	11	10	22	8	4	27	120	80
1943	77	29	25	63	29	28	14	19	11	100	77	57
1944	88	46	92	51	66	74	86	68	80	220	110	56
1945	53	78	74	36	12	14	39	8	8	0	0	0
1946	0	0	0	23	34	150	84	13	24	200	71	70
1947	120	200	47	48	84	190	170	130	110	130	110	110
1948	140	170	200	0	280	0	195	75	12	1100	47	40
1949	110	0	0	0	0	33	0	0	84	0	78	81
1950	120	150	134	100	150	84	130	180	83	89	190	61
1951	300	17	13	0	25	100	240	54	150	200	140	130
1952	320	260	150	27	24	23	14	10	10	150	140	81
1953	130	180	84	0	0	0	0	0	0	0	0	0
1954	0	0	0	0	0	0	0	0	0	0	0	0
1955	0	0	0	0	0	0	0	0	0	0	0	187
1956	237	281	257	25	30	104	132	58	15	143	180	98
1957	98	190	217	0	0	0	0	0	0	0	0	0
1958	0	0	0	0	0	44	0	9	33	137	121	178
1959	135	222	232	161	349	197	213	205	163	235	209	304
1960	277	388	445	490	165	280	214	0	223	219	222	290
1961	262	325	420	238	390	449	436	234	235	302	318	212
1962	280	365	230	198	233	165	351	194	52	124	150	162
1963	143	226	274	240	120	422	133	202	62	0	0	0
1964	0	0	0	0	0	0	0	0	0	0	0	0
1965	0	0	0	0	0	0	0	0	0	0	0	0
1966	0	0	0	0	0	0	0	0	0	0	0	0
1967	0	0	0	0	0	0	0	0	0	0	0	0
1968	0	0	0	0	0	0	0	0	0	0	0	0
1969	0	0	0	0	0	0	0	0	0	0	0	0

APPENDIX 2

CHLORIDE LOAD-FLOW REGRESSION

CURVES

SALT LOAD VS. FLOW AT VERNALIS   PRE CVP   OCTOBER

SALT LOAD VS. FLOW AT VERNALIS   POST CVP   OCTOBER

SALT LOAD VS. FLOW AT VERNALIS   PRE CVP   JANUARY

SALT LOAD VS. FLOW AT VERNALIS   POST CVP   JANUARY

SALT LOAD VS. FLOW AT VERNALIS   PRE CVP   APRIL

SALT LOAD VS. FLOW AT VERNALIS   POST CVP   APRIL

SALT LOAD VS. FLOW AT VERNALIS   PRE CVI

SALT LOAD VS. FLOW AT VERNALIS   POST CVP   JULY

FLOW VS. SALT LOAD   TANISLAUS RIVER   PRE CVP   OCTOBER

```
              11,000        12,000        13,000        14,000        15,00
         10,500      11,500        12,500        13,500        14              15,00
         .+....+....+....+....+....+....+....+....+....+....+....+....+....    +    .+....
 450,000 +                                                                         +  450,000
         :
 412,500 +                                                              *      +  412,500
         :
 375,000 +                                                                /   +  375,000
C        :
H
L
O 337,500 +                                                           /        +  337,500
R        :
I
D
E 300,000 +                                                       /            +  300,000
         :
S
A
L 262,500 +                                                   /                +  262,500
T        :
L
O
A 225,000 +                                              /                     +  225,000
D        :
/
T
O 187,500 +                                        /                           +  187,500
N        :
S
/ 150,000 +                                 /                                   +  150,000
         :                          *
(        :                     /
  112,500 +               *          *                                          +  112,500
         :           /
  75,000 +                                                                      +  75,000
         .+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....
              11,000        12,000        13,000        14,000        15,000
         10,500      11,500        12,500        13,500        14,500
```

FLOW VS. SALT LOAD ON STANISLAUS RIVER   POST C'   OCTOBER

FLOW VS. SALT LOAD ON STANISLAUS RIVER   PRE CVP   JANUARY

FLOW VS. SALT LOAD ON STANISLAUS RIVER   F.   JANUARY

STANISLAUS RIVER FLOW (KAF)

FLOW VS. SALT LOAD ON STANISLAUS RIVER   PRE CVP   APRIL

```
                    45,000        75,000         105,000        135,000         165,000
          30,000        60,000         90,000         120,000        150,000
          ....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+.

   490,000 +        *                                                              +  490,000

   440,000 +                                                                       +  440,000
                                                                        *
 C
 H 390,000 +                                                                       +  390,000
 L
 O
 R
 I 340,000 +                                                                       +  340,000
 D
 E
 S
 A 290,000 +         *                                                             +  290,000
 L
 T
 L
 O 240,000 +                                                                       +  240,000
 A
 D

 / 190,000 +                                                                       +  190,000
 T
 O
 N
 S 140,000 +                                                                       +  140,000
 /

    90,000 +                                                                       +   90,000
                     *
    40,000 +                                                                       +   40,000

          ....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+.
                    45,000        75,000         105,000        135,000         165,000
          30,000        60,000         90,000         120,000        150,000
```

FLOW VS. SALT LOAD ON STANISLAUS RIVER   POST CVP   APRIL

```
                          -.000              60.000            120.000            180.000         240.000
              -30.000         30.000          90.000           150.000          210.000
        ..+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+...

      1840.000 +                                                              *              +  1840.000


      1640.000 +                                                                             +  1640.000


   C  1440.000 +                                                                             +  1440.000
   H
   L
   O
   R  1240.000 +                                                                             +  1240.000
   I
   D
   E
   S  1040.000 +                                                                             +  1040.000
   A
   L
   T
   L   840.000 +                                                                             +   840.000
   O
   A
   D
   /   640.000 +                                                                 *           +   640.000
   T                                                                       *
   O
   N                         *
   S   440.000 +                        *                                                    +   440.000
   /                                                           *  *
                                                                   *
      240.000 +                                                      *                        +   240.000
                            *
                           2*
                           2/
       40.000 +                                                                              +    40.000


        ..+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+...
            -.000           60.000          120.000          100.000           240.000
```

FLOW VS. SALT LOAD ON STANISLAUS RIVE   E CVP   JULY

```
                10,500          13,500                        19,500          22,500
            9,000          12,000          15,000        18,000          21,000
         ..+....+....+....+....+....+....+....+....+....+....  . +....+....+....+....+....+....+....+....+...
                                                                                *
 256,000 +                                          *                                        +  256,000

 246,000 +                                                                                    +  246,000

 236,000 +                                                                                    +  236,000
  C
  H
  L
  O
  R      
  I
  D
 226,000 +                                                                                    +  226,000
  E

  S
  A 216,000 +                                                                                  +  216,000
  L
  T

  L 206,000 +                                                                                  +  206,000
  O
  A
  D

 196,000 +                                                                                    +  196,000
  /
  T
  O
  N 186,000 +                                                                                  +  186,000
  S
  /

 176,000 +                                                                                    +  176,000
                      *
 166,000 +                                                                                    +  166,000
                              *

         ..+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+...
                10,500          13,500          16,500          19,500          22,500
```

FLOW VS. SALT LOAD ON STANISLAUS RIVER   POST CVP   JULY

040796

FLOW VS. SALT LOAD AT MAZE RO.   E   PRE CVP   OCTOBER

FLOW VS. SALT LOAD AT MAZE ROAD BRIDGE   POST CVP   OCTOBER

```
                    45.000        75.000        105.000       135.000          165.000
              30.000        60.000        90.000        120.000       150.000
        ..+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+...
   23400.000 +                                                                    + 23400.000
             .
             .                                                              *
   21900.000 +                                                                    + 21900.000
             .
             .
   20400.000 +                                                                    + 20400.000
C            .
H            .
L            .
O            .
R  18900.000 +                                                                    + 18900.000
I            .
D            .
E            .
S  17400.000 +                                                                    + 17400.000
A            .
L            .
T            .
             .                                                      *
L  15900.000 +                                                                    + 15900.000
O            .
A            .
D            .
             .
/  14400.000 +                   *                                                + 14400.000
T            .                  *
O            .
N  12900.000 +        *     *                          *                     *    + 12900.000
S            .
/            .
             .
   11400.000 +                                             *                      + 11400.000
             .
             .        *
    9900.000 +                                                                    + 9900.000
             .
             .
        ..+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....
```

FLOW VS. SALT LOAD AT HAZE ROAD BRIDGE , PRE CVP   JANU

```
                  80.000            160.000           240.000                  .0            400,000
          40.000           120.000           200.000           280.000    360.000
          ....+....+....+....+....+....+....+....+....+....+....+....+.    ...+....+....+....+.
15450.000 +                                                               + 15450.000

14700.000 +                          *                                    + 14700.000

13950.000 +                                                               + 13950.000
C
H
L
O
R  13200.000 +                                                            + 13200.000
I
D
E
S  12450.000 +                                                        *    + 12450.000
A
L
T
L  11700.000 +                                                            + 11700.000
O
A
D
   10950.000 +                                                            + 10950.000
/
T
O
N
S  10200.000 +                                                            + 10200.000
/
                *

9450.000 +                          *                                     + 9450.000

8700.000 +                                                                + 8700.000


          ....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+.
```

FLOW VS. SALT LOAD AT MAZE ROAD BRIDGE   (CVP   JANUARY

```
                    150,000           450,000            750      9       1050,000         1350,000
              0.000          300,000          600,000         0         1200,000
         +....+....+....+....+....+....+....+....+....+....      .....+....+....+....+....+....+....+
         :
36750.000+                                  *                                              + 36750.000
         :
         :
33000.000+                                                                               + 33000,000
         :                                                                         *
         :
C        :
H 29250.000+                                                                             + 29250.000
L        :
O        :
R        :
I        :
D 25500.000+                   *                                                          + 25500.000
E        :
S        :
A        :
L 21750.000+                                                                             + 21750.000
T        :
         :
L        :
O        :
A 18000.000+              *                                                              + 18000.000
D        :              *
         :
/        :
T 14250.000+        *                                                                    + 14250.000
O        :        *
N        :       *              *                                                        + 10500,000
S        :
/ 10500.000+                                                                             + 10500.000
         :       *
         :
 6750.000+                                                                               + 6750,000
         :
         :                    *
 3000.000+                                                                               + 3000.000
         :
         +....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+
              150,000          450,000          750,000          1050,000         1350,000
```

FLOW VS. SALT LOAD AT HAZE ROAD BRIDGE   PRE CVP   APRIL

```
                    100,000        300,000        500,000        700,000        900,000
           0,000        200,000        400,000        600,000        800,000
           ..+....+....+....+....+....+....+....+....+....+....+....+....+..  ..+....+....+....+....+....+....+..
                                                                              *
22800.000 +                                                                        + 22800.000

21300.000 +                                                                        + 21300.000

C  19800.000 +                                                                      + 19800.000
H
L
O
R  18300.000 +                                                                      + 18300.000
I
D
E
S
A  16800.000 +                                                                      + 16800.000
L
T

L
O  15300.000 +                                                                      + 15300.000
A
D

7  13800.000 +                                                                      + 13800.000
T
O
N
S
/  12300.000 +                                                                      + 12300.000

10800.000 +          *                                                     *        + 10800.000

9300.000 +          *                                                               + 9300.000

          *
           ..+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+..
                    100,000        300,000        500,000        700,000        900,000
```

FLOW VS. SALT LOAD AT MAZE ROAD BRIDGE   CVP   APRIL

FLOW VS. SALT LOAD AT MAZE ROAD BRIDGE   PRE CVP   JULY

FLOW VS. SALT LOAD AT MAZE ROAD BRIDGE   POST CVP   JL

```
                    30,000          90,000          150,000            ,000        270,000
              -,000        60,000        120,000        180,0        240,000
       ....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+.      ...+....+....+....+....+.
       :                                                                              :

  33000,000 +                                                                         +  33000,000
       :                                                                              :
                                                                    *
  29250,000 +                                                                         +  29250,000
       :                                                                              :
  C                                                          *
  H
  L    25500,000 +                                                    *                +  25500,000
  O
  R    :                                                                              :
  I
  D    21750,000 +                                                                    +  21750,000
  E
       :                                                                              :
  S
  A
  L    18000,000 +                                                                    +  18000,000
  T    :                                                                              :
  L
  O
  A    14250,000 +                          *                                         +  14250,000
  D    :                                                                              :

  /
  T    10500,000 +                                                                    +  10500,000
  O    :                                                                              :
  N    *
  S    *
  /    :
       6750,000 +                                                                     +  6750,000
       *   *
  (    :                                                                              :
       *
  3000,000 +                  *                                                        +  3000,000
       :                                                                              :

  -750,000 +                                                                          +  -750,000
       :                                                                              :
       ....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+.
              30,000        90,000        150,000        210,000        270,000
```

FLOW VS. SALT LOAD ON TUOLUMNE RIVER   PRE CVP   OCTOBER

FLOW VS. SALT LOAD ON TUOLUMNE RIVER   POST CVP   OCTOBER

FLOW VS. SALT LOAD ON TUOLUMNE RIVER   PRE CVP   JANUARY

FLOW VS. SALT LOAD ON TUOLUMNE RIVER   POST CVP   JANUARY

FLOW VS. SALT LOAD ON TUOLUMNE RIVER   PRE CVP   APRIL

FLOW VS. SALT LOAD ON TUOLUMNE RIVER FOR CVP   APRIL

FLOW VS. SALT LOAD ON TUOLUMNE RIVER   PRE CV   JULY

FLOW VS. SALT LOAD ON TUOLUMNE RIVER   POST CVP   JULY

```
            30.000          90.000          150.000        21'          270.000
    -.000        60.000         120.000        180.' 0     240.000
 +....+....+....+....+....+....+....+....+....+....+....+..        .....+....+....+....+...I
                                                                                        *|  12200.000
12200.000 +                                                                             +|
        .                                                                               .|
        .                                                                               .|
11200.000 +                                                                             + 11200.000
        .                                                                               .|
 C      .                                                                               .|
 H 10200.000 +                                                                          + 10200.000
 L      .                                                                               .|
 O      .                                                                               .|
 R      .                                                                               .|
 I  9200.000 +                                                                          + 9200.000
 D      .                                                                               .|
 E      .                                                                               .|
        .                     *                                                         .|
 S 8200.000 +                                    .                                      + 8200.000
 A      .                  *                                                            .|
 L      .                                                                               .|
 T      .                                                                               .|
 L  7200.000 +                                                                          + 7200.000
 O      .                                                                               .|
 A      .                                                                               .|
 D      .                                                                               .|
 /  6200.000 +                                                                          + 6200.000
 T      .                                                                               .|
 O      .                                                                               .|
 N      .              *                                                                .|
 S  5200.000 +                                                                          + 5200.000
 /      .            *                                                                  .|
        .          *                                                                    .|
        .         **                                                                    .|
 4200.000 +      *2                                                                     + 4200.000
        .        *                                                                      .|
        .     *                                                                         .|
        .    *                                                                          .|
        .    *                                                                          .|
 3200.000 +    *                                                                        + 3200.000
        .    *                                                                          .|
        .                                                                               .|
 +....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....+....I
```

FLOW VS. SALT LOAD AT GRAYSON   PRE CVP   OCTOBER

FLOW VS. SALT LOAD AT GRAYSON   POST CVP   OBER

FLOW AT GRAYSON (KAF)

FLOW VS. SALT LOAD AT GRAYSON   PRE CVP   JANUARY

FLOW VS. SALT LOAD AT GRAYSON   POST CVP   Y

FLOW VS. SALT LOAD AT GRAYSON   PRE CVP   APRIL

FLOW VS. SALT LOAD AT GRAYSON   POST CVP   APRIL

FLOW VS. SALT LOAD AT GRAYSON   PRE CVP   JULY

FLOW VS. SALT LOAD AT GRAYSON   POST CVP   JULY

FLOW VS. SALT LOAD AT NEWMAN   PRE CVP   OCTOBER

FLOW VS. SALT LOAD AT NEWMAN   POST CV.

FLOW VS. SALT LOAD AT NEWMAN   PRE CVP   JANUARY

040823

FLOW VS. SALT LOAD AT NEWMAN   POST CVP   JANUARY

FLOW VS. SALT LOAD AT NE   RE CVP   APRIL

FLOW VS. SALT LOAD AT NE   RE CVP   APRIL

FLOW VS. SALT LOAD AT NEWMAN   POST CVP   APRIL

FLOW VS. SALT LOAD AT NEWMAN   PRE CVP   JULY

FLOW VS. SALT LOAD AT NEWMAN   POST CVP   JULY

APPENDIX 3

SALT (CHLORIDE) BALANCES BY

REPRESENTATIVE MONTHS

80/05/12.   13.40.05.   OCTOBER   3S   AF UNIMPAIRED AT VERNALIS

DRY YEAR

| FLOW (KAF) | | STATION | CHLORIDES | | | | |
| PRE | POST | | PRE | | POST | | |
			(TONS)	(PCT)	(TONS)	(PCT)	
24.	20.	NEWMAN	3040.	30.	4170.	29.	
16.	16.	OTHF	1960.		2820.		
39.	36.	..N	5000.	49.	6990.	49.	
55.	51.	JLUMNE	3830.	37.	5050.	35.	
5.	9	OTHER	1210.		2540.		
99.		MAZE ROAD	10040.	98.	14570.	102.	
14.	17.	STANISLAUS	260.	3.	200.	1.	
-3.	7.	OTHER	-40.		-470.		
110.	120.	VERNALIS	10260.	100.	14290.	100.	

		TOT. OTHERS	3130.	31.	4890.	34.
		NMN. + OTH.	6170.	60.	9060.	63.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   69. /   324.
POST PPM   =   88. /   383.
DEGRADATION =   19. /   59.

80/05/12.   13.50.38.   JANUARY   110.5 KAF UNIMPAIRED AT VERNALIS

DRY YEAR

FLOW (KAF)		STATION	CHLORIDES			
PRE	POST		PRE (TONS)	(PCT)	POST (TONS)	(PCT)
51.	37.	NEWM^	4240.	48.	8380.	80.
7.	9.	OT	2690.		1310.	
58.	46.	.YSON	6930.	78.	9690.	93.
54.	55.	TUOLUMNE	3490.	39.	4740.	45.
9.	4.	OTHER	580.		-330.	
121.	106.	MAZE ROAD	11010.	123.	14100.	135.
27.	24.	STANISLAUS	130.	1.	170.	2.
2.	3.	OTHER	-2220.		-3850.	
150.	133.	VERNALIS	8920.	100.	10420.	100.
		TOT. OTHERS	1050.	12.	-2870.	-27.
		NMN. + OTH.	5290.	59.	5510.	53.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   44. /   221.
POST PPM   =   58. /   291.
DEGRADATION =   14. /   71.

80/05/12.   14.01.24.   APRIL   601./ AF UNIMPAIRED AT VERNALIS

DRY YEAR

| FLOW (KAF) | | STATION | CHLORIDES | | | |
PRE	POST		PRE (TONS)	(PCT)	POST (TONS)	(PCT)
23.	18.	NEWMAN	5210.	110.	7830.	130.
5.	4.	OTHER	410.		-580.	
28.	22.	GRAYS(	5630.	119.	7250.	120.
26.	21.	MNE	3410.	72.	4420.	73.
-9.	-7.	HER	-190.		-1340.	
43.	3/	MAZE ROAD	8830.	186.	10310.	171.
41.	14.	STANISLAUS	210.	4.	150.	2.
1.	-6.	OTHER	-4300.		-4430.	
86.	44.	VERNALIS	4740.	100.	6030.	100.
		TOT. OTHERS	-4080.	-86.	-6350.	-105.
		NMN. + OTH.	1130.	24.	1480.	25.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   41. /   208.
POST PPM   = 101. /   423.
DEGRADATION =   60. /   215.

80/05/12.   14.12.25.   JULY   101.4 KAF UNIMPAIRED AT VERNALIS

DRY YEAR

FLOW (KAF)		STATION	CHLORIDES				
PRE	POST		PRE (TONS)	(PCT)	POST (TONS)	(PCT)
19.	10.	NEWM	7610.	117.	2670.	59.
4.	2.	⌐	-2540.		490.	
23.	12.	,YSON	5070.	78.	3160.	70.
18.	12.	TUOLUMNE	3690.	57.	3810.	84.
-5.	-⌐	OTHER	-2800.		-1020.	
36.	.	MAZE ROAD	5950.	91.	5940.	131.
12.	6.	STANISLAUS	190.	3.	80.	2.
-1.	-6.	OTHER	390.		-1480.	
46.	18.	VERNALIS	6530.	100.	4540.	100.

TOT. OTHERS	-4950.	-75.	-2010.	-44.
NMN. + OTH.	2660.	41.	660.	15.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   104. /   432.
POST PPM   =   185. /   681.
DEGRADATION =   81. /   249.

80/05/12.   14.03.58.   APRIL   794.9 KAF UNIMPAIRED AT VERNALIS

BELOW NORMAL YEAR

FLOW (KAF) PRE	FLOW (KAF) POST	STATION	CHLORIDES PRE (TONS)	PRE (PCT)	POST (TONS)	POST (PCT)
32.	52.	NEWMAN	5760.	104.	10230.	92.
6.	11.	OTHER	250.		-520.	
38.	63.	GRAYSON	6000.	109.	9710.	88.
33.	61.	TUOLUMNE	3460.	63.	4770.	43.
-11.	-8.	OTHER	-20.		1000.	
60.	115.	MAZE ROAD	9440.	171.	15490.	140.
50.	44.	STANISLAUS	230.	4.	270.	2.
3.	-8.	OTHER	-4130.		-4670.	
113.	150.	VERNALIS	5520.	100.	11080.	100.
		TOT. OTHERS	-3900.	-70.	-4190.	-37.
		NMN. + OTH.	1860.	34.	6040.	55.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   36. / 187.
POST PPM   =   54. / 279.
DEGRADATION =   18. /   91.

```
80/05/12.      14.15.13.     JULY          224.9 KAF UNIMPAIRED AT VERNALIS

BELOW NORMAL YEAR
```

FLOW (KAF)		STATION	CHLORIDES			
PRE	POST		PRE		POST	
			(TONS)	(PCT)	(TONS)	(PCT)
27.	19.	_WMAN	7690.	96.	4370.	57.
7.	5.	OTHER	-1890.		1060.	
34.	24.	GRAYSON	5790.	72.	5430.	71.
23.	23.	TUOLUMNE	3720.	46.	4260.	55.
-5.	-5.	OTHER	-2090.		-480.	
51.	42.	MAZE ROAD	7420.	93.	9210.	120.
14.	12.	STANISLAUS	210.	3.	140.	2.
0.	-8.	OTHER	390.		-1640.	
64.	46.	VERNALIS	8020.	100.	7700.	100.
		TOT. OTHERS	-3590.	-44.	-1060.	-13.
		NMN. + OTH.	4100.	51.	3310.	43.

```
QUALITY PPM     (CL) / (TDS)

PRE PPM      =    92. /   396.
POST PPM     =   123. /   491.
DEGRADATION  =    31. /    95.
```

80/05/12.   13.45.43.   OCTOBER   42.4 KAF UNIMPAIRED AT VERNALIS

ABOVE NORMAL YEAR

FLOW (KAF)		STATION	CHLORIDES			
PRE	POST		PRE		POST	
			(TONS)	(PCT)	(TONS)	(PCT)
19.	12.	NEWMAN	2960.	31.	3190.	34.
13.	11.	OTHER	1310.		2650.	
33.	23.	GRAYSON	4270.	45.	5840.	63.
52.	32.	TUOLUMNE	3820.	40.	4580.	49.
4.	2.	OTHER	1480.		2700.	
89.	57.	MAZE ROAD	9570.	101.	13120.	141.
13.	11.	STANISLAUS	210.	2.	160.	2.
-4.	-3.	OTHER	-330.		-3990.	
98.	65.	VERNALIS	9440.	100.	9280.	100.
		TOT. OTHERS	2460.	26.	1360.	15.
		NMN. + OTH.	5420.	57.	4550.	49.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   71. /   331.
POST PPM   =   105. /   435.
DEGRADATION =   34. /   104.

80/05/12.   13.56.03.   JANUARY   352.5 KAF UNIMPAIRED AT VERNALIS

ABOVE NORMAL YEAR

FLOW (KAF)		STATION	CHLORIDES			
PRE	POST		PRE		POST	
			(TONS)	(PCT)	(TONS)	(PCT)
130.	80.	NEWMAN	7130.	54.	10160.	70.
11.	14.	OTHER	1560.		350.	
141.	94.	GRAYSON	8700.	66.	10510.	73.
81.	111.	TUOLUMNE	3750.	29.	5080.	35.
6.	-4.	OTHER	-630.		400.	
229.	201.	MAZE ROAD	11810.	90.	16000.	111.
51.	56.	STANISLAUS	180.	1.	270.	2.
0.	6.	OTHER	1140.		-1820.	
279.	263.	VERNALIS	13130.	100.	14450.	100.
		TOT. OTHERS	2070.	16.	-1070.	-7.
		NMN. + OTH.	9200.	70.	9090.	63.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   35. /   183.
POST PPM   =   40. /   236.
DEGRADATION =   5. /   53.

80/05/12.   14.06.23.   APRIL   1055.7 KAF UNIMPAIRED AT VERNALIS

ABOVE NORMAL YEAR

| FLOW (KAF) | | STATION | CHLORIDES | | | |
PRE	POST		PRE (TONS)	(PCT)	POST (TONS)	(PCT)
366.	84.	NEWMAN	11730.	70.	11570.	79.
46.	17.	OTHER	-2170.		-450.	
413.	102.	GRAYSON	9550.	57.	11110.	76.
199.	98.	TUOLUMNE	3880.	23.	4950.	34.
-2.	-3.	OTHER	1730.		2610.	
609.	196.	MAZE ROAD	15160.	91.	18680.	127.
190.	74.	STANISLAUS	400.	2.	370.	3.
5.	-6.	OTHER	1100.		-4370.	
805.	264.	VERNALIS	16660.	100.	14670.	100.
		TOT. OTHERS	660.	4.	-2210.	-15.
		NMN. + OTH.	12390.	74.	9360.	64.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   15. /   101.
POST PPM   =   41. /   239.
DEGRADATION =   26. /   138.

80/05/12.   14.17.48.   JULY   425.1 KAF UNIMPAIRED AT VERNALIS

ABOVE NORMAL YEAR

| FLOW (KAF) | | STATION | | CHLORIDES | | | |
| PRE | POST | | | PRE | | POST | |
				.TONS)	(PCT)	(TONS)	(PCT)
108.	25.	NEWMA'		8000.	44.	5540.	56.
33.	9.	OTF'		1830.		1510.	
141.	34.	SON		9830.	55.	7040.	71.
55.	31.	OLUMNE		3860.	21.	4490.	45.
3.		OTHER		4010.		-170.	
200.	62.	MAZE ROAD		17710.	98.	11360.	115.
28.	17.	STANISLAUS		330.	2.	170.	2.
7.	-7.	OTHER		-10.		-1620.	
235.	72.	VERNALIS		18020.	100.	9910.	100.
		TOT. OTHERS		5830.	32.	-280.	-2.
		NMN. + OTH.		13830.	77.	5260.	53.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   56. /   270.
POST PPM   =   101. /   423.
DEGRADATION =   45. /   153.

80/05/12.   13.48.12.   OCTOBER   29.8 KAF UNIMPAIRED AT VERNALIS

WET YEAR

FLOW (KAF)		STATION		CHLORIDES			
PRE	POST			PRE		POST	
				(TONS)	(PCT)	(TONS)	(PCT)
22.	15.	NEWMAN		3020.	30.	3620.	32.
15.	13.	OTHER		1800.		2740.	
38.	28.	GRAYSON		4820.	48.	6360.	56.
54.	40.	TUOLUMNE		3830.	38.	4800.	42.
5.	5.	OTHER		1280.		2630.	
97.	73.	MAZE ROAD		9930.	99.	13790.	121.
14.	14.	STANISLAUS		240.	2.	180.	2.
-3.	0.	OTHER		-110.		-2570.	
107.	87.	VERNALIS		10060.	100.	11400.	100.
		TOT. OTHERS		2970.	30.	2800.	25.
		NMN. + OTH.		5990.	60.	6420.	56.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   69. /   324.
POST PPM   =   96. /   408.
DEGRADATION   =   27. /   84.

80/05/12.   13.58.57.   JANUARY   695.7 KAF UNIMPAIRED AT VERNALIS

WET YEAR

FLOW (KAF) PRE	FLOW (KAF) POST	STATION	CHLORIDES PRE (TONS)	PRE (PCT)	CHLORIDES POST (TONS)	POST (PCT)
233.	246.	NEWMAN	9850.	59.	13480.	58.
13.	2.	OTHER	160.		-1630.	
296.	268.	GRAYSON	10010.	60.	11850.	51.
104.	310.	TUOLUMNE	3910.	23.	5630.	24.
-10.	-61.	OTHER	-1590.		1770.	
339.	516.	MAZE ROAD	12330.	74.	19250.	83.
75.	185.	STANISLAUS	220.	1.	530.	2.
-4.	13.	OTHER	4140.		3540.	
410.	714.	VERNALIS	16690.	100.	23320.	100.
		TOT. OTHERS	2710.	16.	3680.	16.
		NMN. + OTH.	12560.	75.	17160.	74.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   163. /   30.
POST PPM   =   187. /   24.
DEGRADATION   =   -6. /   24.

* NOTE: 040842
PCT COLUMN IS PERCENT OF VERNALIS.

80/05/12.　　　14.09.13.　　　APRIL　　　　　1169.0 KAF UNIMPAIRED AT VERNALIS

WET YEAR

FLOW (KAF)		STATION	CHLORIDES				
PRE	POST		PRE		POST		
			(TONS)	(PCT)	(TONS)	(PCT)	
585.	267.	NEWMAN	13450.	65.	15470.	54.	
67.	47.	OTHER	-3000.		-190.		
652.	314.	GRAYSON	10450.	51.	15270.	54.	
281.	306.	TUOLUMNE	3960.	19.	5390.	19.	
19.	73.	OTHER	2190.		8380.		
952.	693.	MAZE ROAD	16600.	81.	29040.	102.	
246.	256.	STANISLAUS	450.	2.	720.	3.	
-23.	51.	OTHER	3560.		-1340.		
1175.	1000.	VERNALIS	20620.	100.	28410.	100.	

TOT. OTHERS	2750.	13.	6850.	24.
NMN. + OTH.	16200.	79.	22320.	79.

QUALITY PPM　　(CL) / (TDS)

PRE PPM　　　=　　13. /　　92.
POST PPM　　=　　21. /　　178.
DEGRADATION =　　8. /　　85.

80/05/12.   14.20.10.   JULY   921.0 KAF UNIMPAIRED AT VERNALIS

WET YEAR

FLOW (KAF)		STATION	CHLORIDES			
PRE	POST		PRE (TONS)	(PCT)	POST (TONS)	(PCT)
365.	65.	NEWMAN	8280.	23.	11740.	53.
129.	40.	OTHER	7300.		4360.	
494.	105.	GRAYSON	15580.	43.	16100.	73.
119.	80.	TUOLUMNE	3980.	11.	5320.	24.
49.	29.	OTHER	18210.		720.	
662.	214.	MAZE ROAD	37780.	104.	22140.	100.
50.	51.	STANISLAUS	480.	1.	360.	2.
17.	34.	OTHER	-1780.		-360.	
730.	300.	VERNALIS	36470.	100.	22130.	100.
		TOT. OTHERS	23730.	65.	4720.	21.
		NMN. + OTH.	32010.	88.	16460.	74.

QUALITY PPM   (CL) / (TDS)

PRE PPM   =   37. /   192.
POST PPM   =   54. /   279.
DEGRADATION =   17. /   87.

APPENDIX 4

SUMMARY OF NETWORK ANALYSES OF THE

LOWER SACRAMENTO-SAN JOAQUIN DELTA

R. F. Blanks   February 16, 1951

D. J. Hebert and W. B. McBirney

Summary of network analyses of lower Sacramento-San Joaquin Delta

    1. The results of all network analyses of the lower Sacramento-San Joaquin Delta have been summarized on the six diagrams attached. Rate and direction of flow are shown on one side of a channel, and a resistance value based on channel characteristics is given on the other side. Resistances were computed from $r = \dfrac{L \times 10^4}{b^2 d^{10/3}}$. Three channels NL, LK, and KQ, are very large and have been assumed at constant level regardless of discharge. Computations made to test this premise show that a large increase in discharge can be accommodated by a negligible increase in slope. The wavy connection shown from S to Q represents channels NS, LS, and KS, and the resistance value used is the hydraulic equivalent of the three channels having S as a common point and terminating at N, L, K, or Q.

    2. The first few schemes tried made use of resistance values which were derived from channel cross-sections as shown on available maps. It became evident they gave a division of flow which was contrary to that actually prevailing, and therefore at points such as 7 and 8, the resistances of connecting channels were arbitrarily adjusted until the division was more nearly correct. Thus, in channel (7-8) the resistance was changed to 26.2 and to 0.832 from 239.0, and in channel 8-Y, the resistance was increased to 10.0 from 8.65. Resistance in channel 6-7 was decreased to 2.0 from 7.41.

    3. The results of the network analysis can be used to estimate the drop in water surface from Central Landing to Tracy Pumping Plant when the pumps are working at design capacity of 4,600 cubic feet per second. For mean tide height in the lower Delta this drop has been estimated to be 0.25 foot. Were the levels to be at mean low tide height an increase to approximately 0.34 foot may be expected. Making allowance for indeterminate factors, it is thought the maximum head loss, or draw-down, to Tracy Pumping Plant will be about 0.5 foot.

DELTA NETWORK ANALYSIS

Q=

Q=

K Central Ldg.

Q= 2280

L

1969
0.00809

0.0247
740

0.29

0.013

S   0.414 U
206

0.218
184

0.247
184

W

0.025
613

Q=

N

A

2175
0.069

718
1.29

Y   Stockton

613

8.65

T

0.097
1825

0.751
527

Q= 350
Contra-Costa

Q= 360

4591
0.105

0.777
646

4

16.1
119

7   26.2
387

7.41
26.3

8

HEAD LOSS Q TO 5 = 0.07'

Q= 2500
Delta-Mendota

0.618
198

Q= 70

Q= 1000

SCHEME __7__ TRIAL _FINAL_

DELTA NETWORK ANALYSIS

K Central Ldg.

Q=438.0

L

Q=

Q=

3325
0.00809   0.0247
1297   Q   0.013
242

S   0.414   U
340

0.0247

0.218   0.247   W
302   V   302   544   0.025

N

3665
0.069

1259
129

Stockto

544   6.65

T   0.097
3315
Q=350
Contra-Costa

M   0.751
1080
Q=360

4

16.1
75

3134   0.195   0.777
1155

7   26.2
456   8

7.41
381

Q=4600   5   0.618
Delta-Mendota   311

Q=70   Q=1000

·HEAD LOSS Q TO 5 = 0.22'

SCHEME   8   TRIAL   FINAL

DELTA NETWORK ANALYSIS

HEAD LOSS Q TO 5 = 0.25'

SCHEME __9__ TRIAL _FINAL_

DELTA NETWORK ANALYSIS

HEAD LOSS Q TO 5 = 0.07'

SCHEME __11__ TRIAL __FINAL__

DELTA NETWORK ANALYSIS

HEAD LOSS Q TO   0.18'

SCHEME _13_ TRIAL _FINAL_

DELTA NETWORK ANALYSIS

$Q =$

$Q =$

K central Ldg.

$Q = 4380$

L

2902
0.00809

0.0247
1130

0.013
948

S

0.414
2.96

U

0.218
254

0.247
254

V

W

0.025
94

N

3198
0.069

6.900

1088
1.29

Y   Stockton

A

94
10.0

94
10.0

T

$Q = 350$
Contra-Costa

0.097
2848

N

0.751
847

$Q = 360$

2726
(81)

0.191

4

18.0
234

0.777
1081

7   0.832
1094

2.0
860

8

$Q = 4600$
Delta-Mendota

5

0.618
790

$Q = 70$

$Q = 1000$

HEAD LOSS Q TO S = 0.17'

SCHEME __14__ TRIAL _FINAL_